



TEMPORARY PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY		TOTAL QUANTITY
			BREAKDOWN		
PAVEMENT MARKING LINES					
PAINT (4")					
PA	WHITE EDGELINE(2X)		14,370	LF	
PI	YELLOW DOUBLE CENTER(2X)		16,250	LF	
PH	YELLOW SINGLE CENTER (2X)		4,960	LF	
PF	10 FT. YELLOW SKIP (2X)		1,240	LF	
			TOTAL		36,820 LF
MARKERS					
TEMPORARY RAISED PAVEMENT MARKERS					
MH	YELLOW & YELLOW		163	EA	
			TOTAL		163 EA

- NOTES: 1) FOR EACH PAINT PAVEMENT MARKING ITEM, 2X MEANS TWO APPLICATIONS.
2) AS DIRECTED BY THE ENGINEER, TEMPORARY PAVEMENT MARKING (PAINT) MAY BE USED TO STRIPE THE FINAL TRAFFIC PATTERN ON THE -L- LINE. THE TEMPORARY PAVEMENT MARKING SCHEDULE INCLUDES QUANTITIES FOR PLACING TWO APPLICATIONS OF PAINT ON THE FINAL SURFACE OF NEW ASPHALT WITH PERMANENT TRAFFIC PATTERNS WHICH WILL REMAIN IN PLACE UNTIL THE PROPOSED FINAL PAVEMENT MARKING (THERMOPLASTIC) IS APPLIED.

APPROVED: *Michelle A. Brane* DATE: 11/3/04

OVERVIEW 1 & TEMPORARY PAVEMENT MARKING SCHEDULE

SCALE: NONE		REVISIONS
DATE: 8-6-04		
DWG. BY: JMS		
DESIGN BY: MRB		

REVIEWED BY: MRB

SYSTEMS
 DESIGN
 SERVICES