

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0005	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	250 TON		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	160 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	2,000 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	2,000 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	360 SF		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	200 TON		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	253 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	360 LF		
0013	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	234 LF		
0014	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	454 LF		
0015	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (72", 138")	234 LF		
0016	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	224 LF		
0017	0654000000-E	310	**** X **** CS PIPE ARCH CULVERTS, ***** THICK (142" X 91", 0.138")	78 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	92 LF		
0019	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0020	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0021	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	2 EA		
0022	0995000000-E	340	PIPE REMOVAL	706 LF		
0023	1220000000-E	545	INCIDENTAL STONE BASE	75 TON		
0024	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/4")	180 SY		
0025	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,400 TON		
0026	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,000 TON		
0027	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,400 TON		
0028	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	300 TON		
0029	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0030	2000000000-N	806	RIGHT OF WAY MARKERS	23 EA		
0031	2022000000-E	815	SUBDRAIN EXCAVATION	60 CY		
0032	2033000000-E	815	SUBDRAIN FINE AGGREGATE	45 CY		
0033	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	250 LF		
0034	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0035	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	23 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	18.86	LF	
0037	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	8	EA	
0038	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2	EA	
0039	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	5	EA	
0040	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	8	EA	
0041	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	2,600	LF	
0042	2556000000-E	846	SHOULDER BERM GUTTER	1,580	LF	
0043	2580000000-E	846	CONCRETE VALLEY GUTTER	150	LF	
0044	2591000000-E	848	4" CONCRETE SIDEWALK	715	SY	
0045	2598000000-E	848	CONCRETE WHEELCHAIR RAMPS	90	SY	
0046	2830000000-N	858	ADJUSTMENT OF MANHOLES	1	EA	
0047	3030000000-E	862	STEEL BM GUARDRAIL	512.5	LF	
0048	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50	LF	
0049	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0050	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1	EA	
0051	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8	EA	
0052	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	7	EA	
0053	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	412.5	LF	

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	2 EA		
0055	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6 EA		
0056	3642000000-E	876	PLAIN RIP RAP, CLASS A	55 TON		
0057	3649000000-E	876	PLAIN RIP RAP, CLASS B	55 TON		
0058	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	875 SY		
0059	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	9 EA		
0060	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	12 SF		
0061	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	10 SF		
0062	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	95 LF		
0063	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0064	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0065	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	6 EA		
0066	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	132 SF		
0067	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	176 SF		
0068	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	154 SF		
0069	4430000000-N	1130	DRUMS	100 EA		
0070	4435000000-N	1135	CONES	20 EA		
0071	4446100000-E	SP	BARRICADES (TYPE III)	174 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	4450000000-N	1150	FLAGGER	320 HR		
0073	4485000000-E	1170	PORTABLE CONCRETE BARRIER	80 LF		
0074	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	200 LF		
0075	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	163 EA		
0076	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	720 LF		
0077	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	4,310 LF		
0078	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	8 EA		
0079	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	36,820 LF		
0080	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	80 EA		
0081	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0082	5300000000-E	1505	FOUNDATION CONDITIONING MATE- RIAL, UTILITIES CLASS ***** (VI)	25 TON		
0083	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	25 TON		
0084	5360000000-E	1510	6" DI WATER PIPE, PC 350	59 LF		
0085	5384000000-E	1510	16" DI WATER PIPE, PC ***** (350)	236 LF		
0086	5414000000-E	1510	3/4" COPPER WATER PIPE, TYPE K	60 LF		
0087	5480000000-E	1510	DUCTILE IRON WATER PIPE FIT- TINGS, 250# MIN WP	1,035 LB		
0088	5648000000-N	1510	RELOCATE EXISTING WATER METER	2 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	5666000000-E	1510	FIRE HYDRANT, *****# WP (150)	2	EA	
0090	5810000000-E	1530	FILL OR REMOVE ABANDONED 16" PIPE, ***** (DI - WATER)	450	LF	
0091	5882000000-N	SP	GENERIC UTILITY ITEM 16" GATE VALVE AND VALVE MAN- HOLE,200#WP	1	EA	
0092	5888000000-E	SP	GENERIC UTILITY ITEM 20" HDPE WATER PIPE, SDR 9, 200 # WP BY DIRECTIONAL BORE	230	LF	
0093	6000000000-E	1605	TEMPORARY SILT FENCE	1,900	LF	
0094	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	175	TON	
0095	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	675	TON	
0096	6012000000-E	1610	SEDIMENT CONTROL STONE	475	TON	
0097	6015000000-E	1615	TEMPORARY MULCHING	3	ACR	
0098	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0099	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5	TON	
0100	6024000000-E	1622	TEMPORARY SLOPE DRAINS	150	LF	
0101	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	5	EA	
0102	6030000000-E	1630	SILT EXCAVATION	1,450	CY	
0103	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,210	SY	
0104	6042000000-E	1632	1/4" HARDWARE CLOTH	300	LF	
0105	6070000000-N	SP	SPECIAL STILLING BASINS	6	EA	
0106	6084000000-E	1660	SEEDING & MULCHING	4	ACR	

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	6087000000-E	1660	MOWING	1.5 ACR		
0108	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0109	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0110	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0111	6108000000-E	1665	FERTILIZER TOPDRESSING	3 TON		
0112	6114000000-N	SP	SPECIALIZED HAND MOWING	4 HR		
0113	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	12 EA		
0114	6123000000-E	1670	REFORESTATION	1 ACR		
STRUCTURE ITEMS						
0115	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (22+37.00 -L-)	Lump Sum	L.S.	
0116	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (14+31.00 -L-)	Lump Sum	L.S.	
0117	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+31.00 -L-)	Lump Sum	L.S.	
0118	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22+37.00 -L-)	Lump Sum	L.S.	
0119	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SO IL	54.6 LF		
0120	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	25.5 LF		
0121	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	54.6 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0122	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0123	8116000000-E	SP	CSL TUBES	350.4 LF		
0124	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	1,646 CY		
0125	8161000000-E	420	GROOVING BRIDGE FLOORS	10,400 SF		
0126	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	111.2 CY		
0127	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	211.5 CY		
0128	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+31.00 -L-)	Lump Sum	L.S.	
0129	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+37.00 -L-)	Lump Sum	L.S.	
0130	8217000000-E	425	REINFORCING STEEL (BRIDGE)	35,862 LB		
0131	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	2,723 LB		
0132	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,998 LB		
0133	8364000000-E	450	HP12X53 STEEL PILES	1,060 LF		
0134	8384000000-E	450	HP14X73 STEEL PILES	960 LF		
0135	8406000000-N	SP	GALVANIZING STEEL PILES AT STA ***** (22+37.00 -L-)	Lump Sum	L.S.	
0136	8482000000-E	460	THREE BAR METAL RAIL	360.4 LF		
0137	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	489 TON		
0138	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	544 SY		
0139	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County: Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0140	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0141	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	3,901.67 LF		
0142	8892000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE WEARING SURFACE	9,040 SF		
1031/Mar16/Q145207.98/D627281180000/E142			Total Amount Of Bid For Entire Project :			

C200841 (B-3450)
COUNTY: DURHAM

2/16/99

Contract No: C200841
County: Durham

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General