

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
**SUMMARY OF QUANTITIES**

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201070														
ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000010000-N	800	Lump Sum		MOBILIZATION	206600000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+06.00)	207700000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)	602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
004300000-N	226	Lump Sum		GRADING	228600000-N	840	5	EA	MASONRY DRAINAGE STRUCTURES	602900000-E	SP	185	LF	SAFETY FENCE
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING	235500000-N	840	4	EA	FRAME WITH GRATE, STD 840.29	603000000-E	1630	210	CY	SILT EXCAVATION
005700000-E	226	600	CY	UNDERCUT EXCAVATION	239600000-N	840	1	EA	FRAME WITH COVER, STD 840.54	603600000-E	1631	725	SY	MATting FOR EROSION CONTROL
008000000-E	SP	600	TON	CLASS IV SUBGRADE STABILIZATION	255600000-E	846	355	LF	SHOULDER BERM GUTTER	604200000-E	1632	80	LF	1/4" HARDWARE CLOTH
013400000-E	240	14	CY	DRAINAGE DITCH EXCAVATION	303000000-E	862	350	LF	STEEL BM GUARDRAIL	607000000-N	SP	4	EA	SPECIAL STILLING BASINS
019500000-E	265	500	CY	SELECT GRANULAR MATERIAL	304500000-E	862	25	LF	STEEL BM GUARDRAIL, SHOP CURVED	608400000-E	1660	1	ACR	SEEDING & MULCHING
019600000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION	315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	608700000-E	1660	0.5	ACR	MOWING
031800000-E	300	40	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	319500000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1	609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
034300000-E	310	40	LF	15" SIDE DRAIN PIPE	321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
034500000-E	310	32	LF	24" SIDE DRAIN PIPE	327000000-N	SP	2	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
036600000-E	310	224	LF	15" RC PIPE CULVERTS, CLASS III	362800000-E	876	55	TON	PLAIN RIP RAP, CLASS I	610800000-E	1665	0.75	TON	FERTILIZER TOPDRESSING
037800000-E	310	44	LF	24" RC PIPE CULVERTS, CLASS III	364900000-E	876	3	TON	PLAIN RIP RAP, CLASS B	611400000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
070800000-E	310	20	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	365600000-E	876	460	SY	FILTER FABRIC FOR DRAINAGE	611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
080600000-E	310	2	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	365900000-N	SP	1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	612300000-E	1670	0.1	ACR	REFORESTATION
122000000-E	545	100	TON	INCIDENTAL STONE BASE	441200000-E	SP	230	SF	WORK ZONE SIGNS (STATIONARY)					
148900000-E	610	135	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	441220000-E	SP	56	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)					
152500000-E	SP	310	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	444610000-E	SP	96	LF	BARRICADES (TYPE III)					
156000000-E	620	26	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	481000000-E	1205	2,600	LF	PAINT PAVEMENT MARKING LINES (4")					
202200000-E	815	112	CY	SUBDRAIN EXCAVATION	600000000-E	1605	725	LF	TEMPORARY SILT FENCE					
203300000-E	815	84	CY	SUBDRAIN FINE AGGREGATE	600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A					
204400000-E	815	500	LF	6" PERFORATED SUBDRAIN PIPE	600900000-E	1610	180	TON	STONE FOR EROSION CONTROL, CLASS B					
205500000-E	815	15	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	601200000-E	1610	165	TON	SEDIMENT CONTROL STONE					
					601500000-E	1615	1	ACR	TEMPORARY MULCHING					

5/28/99  
03-NOV-2004 10:32  
R:\Roadway\Proj\B4180\_rdy\_tsh.dgn  
MRHussey