

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201201

ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+70.00)
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
005700000-E	226	450	CY	UNDERCUT EXCAVATION
006300000-N	SP	Lump Sum		GRADING
010600000-E	230	7,500	CY	BORROW EXCAVATION
031800000-E	300	85	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
036600000-E	310	572	LF	15" RC PIPE CULVERTS, CLASS III
070800000-E	310	220	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
080600000-E	310	6	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
122000000-E	545	100	TON	INCIDENTAL STONE BASE
148900000-E	610	625	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
152500000-E	SP	375	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
156000000-E	620	53	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
220900000-E	838	1	CY	ENDWALLS
228600000-N	840	8	EA	MASONRY DRAINAGE STRUCTURES
230800000-E	840	3	LF	MASONRY DRAINAGE STRUCTURES
236600000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.24
236700000-N	840	5	EA	FRAME WITH TWO GRATES, STD 840.29
255600000-E	846	650	LF	SHOULDER BERM GUTTER
258000000-E	846	30	LF	CONCRETE VALLEY GUTTER
303000000-E	862	1,000	LF	STEEL BM GUARDRAIL
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III

ItemNumber	Sec #	Quantity	Unit	Description
327000000-N	SP	6	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
365600000-E	876	660	SY	FILTER FABRIC FOR DRAINAGE
365900000-N	SP	3	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
441200000-E	SP	320	SF	WORK ZONE SIGNS (STATIONARY)
441220000-E	SP	122	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
442500000-N	1125	4	EA	WARNING FLAG SETS
443000000-N	1130	20	EA	DRUMS
444610000-E	SP	120	LF	BARRICADES (TYPE III)
481000000-E	1205	8,400	LF	PAINT PAVEMENT MARKING LINES (4")
490000000-N	1252	13	EA	PERMANENT RAISED PAVEMENT MARKERS
600000000-E	1605	825	LF	TEMPORARY SILT FENCE
600600000-E	1610	150	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	225	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	465	TON	SEDIMENT CONTROL STONE
601500000-E	1615	3	ACR	TEMPORARY MULCHING
601800000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEED- ING
602400000-E	1622	100	LF	TEMPORARY SLOPE DRAINS
602700000-N	1622	3	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
602900000-E	SP	300	LF	SAFETY FENCE
603000000-E	1630	1,230	CY	SILT EXCAVATION
603600000-E	1631	1,950	SY	MATTING FOR EROSION CONTROL
604200000-E	1632	740	LF	1/4" HARDWARE CLOTH
607000000-N	SP	8	EA	SPECIAL STILLING BASINS
608400000-E	1660	3.5	ACR	SEEDING & MULCHING

ItemNumber	Sec #	Quantity	Unit	Description
608700000-E	1660	2	ACR	MOWING
609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	75	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	2.5	TON	FERTILIZER TOPDRESSING
611400000-N	SP	3	HR	SPECIALIZED HAND MOWING
611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL