PROJ. REFERENCE NO.	SHEET NO.
B-3875	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
9+50.000	0	0
10+00.000	0	15
10+50.000	0	26
11+00.000	0	19
11+50.000	1	18
12+00.000	28	124
12+50.000	48	450
13+00.000	30	538
13+50.000	16	288
14+00.000	6	190
14+50.000	0	327
15+00.000	0	544
15+50.000	0	753
16+00.000	0	920
16+50.000	0	1468
19+00.000	83	637
19+50.000	200	227
20+00.000	336	77
20+50.000	367	26
21+00.000	369	20
21+50.000	199	14
21+75.000	7	2