

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201203

| ItemNumber | Sec # | Quantity | Unit | Description |
|--------------|-------|----------|------|---|
| 0000100000-N | 800 | Lump Sum | | MOBILIZATION |
| 0022000000-E | 225 | 4,600 | CY | UNCLASSIFIED EXCAVATION |
| 0029000000-N | SP | Lump Sum | | REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+23.47) |
| 0043000000-N | 226 | Lump Sum | | GRADING |
| 0050000000-E | 226 | 1 | ACR | SUPPLEMENTARY CLEARING & GRUBBING |
| 0057000000-E | 226 | 100 | CY | UNDERCUT EXCAVATION |
| 0080000000-E | SP | 500 | TON | CLASS IV SUBGRADE STABILIZATION |
| 0195000000-E | 265 | 500 | CY | SELECT GRANULAR MATERIAL |
| 0196000000-E | 270 | 500 | SY | FABRIC FOR SOIL STABILIZATION |
| 0318000000-E | 300 | 22 | TON | FOUNDATION CONDITIONING MATERIAL, MINOR STRS |
| 0343000000-E | 310 | 72 | LF | 15" SIDE DRAIN PIPE |
| 0366000000-E | 310 | 108 | LF | 15" RC PIPE CULVERTS, CLASS III |
| 0708000000-E | 310 | 20 | LF | 15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK |
| 0806000000-E | 310 | 2 | EA | 15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK |
| 0995000000-E | 340 | 47 | LF | PIPE REMOVAL |
| 1220000000-E | 545 | 50 | TON | INCIDENTAL STONE BASE |
| 1489000000-E | 610 | 470 | TON | ASPHALT CONC BASE COURSE, TYPE B25.0B |
| 1525000000-E | SP | 370 | TON | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A |
| 1560000000-E | 620 | 45 | TON | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 |
| 2022000000-E | 815 | 224 | CY | SUBDRAIN EXCAVATION |
| 2033000000-E | 815 | 168 | CY | SUBDRAIN FINE AGGREGATE |
| 2044000000-E | 815 | 1,000 | LF | 6" PERFORATED SUBDRAIN PIPE |
| 2055000000-E | 815 | 30 | EA | 6" SUBDRAIN PIPE WYES, TEES, & ELBOWS |
| 2066000000-N | 815 | 2 | EA | CONCRETE PAD FOR SUBDRAIN PIPE OUTLET |

| ItemNumber | Sec # | Quantity | Unit | Description |
|--------------|-------|----------|------|---|
| 2077000000-E | 815 | 12 | LF | 6" OUTLET PIPE (SUBDRAINS) |
| 2286000000-N | 840 | 3 | EA | MASONRY DRAINAGE STRUCTURES |
| 2367000000-N | 840 | 3 | EA | FRAME WITH TWO GRATES, STD 840.29 |
| 2556000000-E | 846 | 320 | LF | SHOULDER BERM GUTTER |
| 3030000000-E | 862 | 600 | LF | STEEL BM GUARDRAIL |
| 3150000000-N | 862 | 5 | EA | ADDITIONAL GUARDRAIL POSTS |
| 3215000000-N | 862 | 4 | EA | GUARDRAIL ANCHOR UNITS, TYPE III |
| 3270000000-N | SP | 4 | EA | GUARDRAIL ANCHOR UNITS, TYPE 350 |
| 3628000000-E | 876 | 23 | TON | PLAIN RIP RAP, CLASS I |
| 3649000000-E | 876 | 3 | TON | PLAIN RIP RAP, CLASS B |
| 3656000000-E | 876 | 739 | SY | FILTER FABRIC FOR DRAINAGE |
| 3659000000-N | SP | 1 | EA | PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON |
| 4412000000-E | SP | 225 | SF | WORK ZONE SIGNS (STATIONARY) |
| 4412200000-E | SP | 94 | SF | WORK ZONE SIGNS (BARRICADE MOUNTED) |
| 4446100000-E | SP | 100 | LF | BARRICADES (TYPE III) |
| 4810000000-E | 1205 | 7,200 | LF | PAINT PAVEMENT MARKING LINES (4") |
| 6000000000-E | 1605 | 325 | LF | TEMPORARY SILT FENCE |
| 6006000000-E | 1610 | 75 | TON | STONE FOR EROSION CONTROL, CLASS A |
| 6009000000-E | 1610 | 150 | TON | STONE FOR EROSION CONTROL, CLASS B |
| 6012000000-E | 1610 | 350 | TON | SEDIMENT CONTROL STONE |
| 6015000000-E | 1615 | 3.5 | ACR | TEMPORARY MULCHING |
| 6018000000-E | 1620 | 150 | LB | SEED FOR TEMPORARY SEEDING |
| 6021000000-E | 1620 | 0.5 | TON | FERTILIZER FOR TEMPORARY SEEDING |
| 6029000000-E | SP | 200 | LF | SAFETY FENCE |
| 6030000000-E | 1630 | 700 | CY | SILT EXCAVATION |

| ItemNumber | Sec # | Quantity | Unit | Description |
|--------------|-------|----------|------|----------------------------------|
| 6036000000-E | 1631 | 1,400 | SY | MATTING FOR EROSION CONTROL |
| 6038000000-E | SP | 25 | SY | PERMANENT SOIL REINFORCEMENT MAT |
| 6042000000-E | 1632 | 80 | LF | 1/4" HARDWARE CLOTH |
| 6070000000-N | SP | 12 | EA | SPECIAL STILLING BASINS |
| 6084000000-E | 1660 | 3.5 | ACR | SEEDING & MULCHING |
| 6087000000-E | 1660 | 2 | ACR | MOWING |
| 6090000000-E | 1661 | 50 | LB | SEED FOR REPAIR SEEDING |
| 6093000000-E | 1661 | 0.25 | TON | FERTILIZER FOR REPAIR SEEDING |
| 6096000000-E | 1662 | 75 | LB | SEED FOR SUPPLEMENTAL SEEDING |
| 6108000000-E | 1665 | 2.5 | TON | FERTILIZER TOPDRESSING |
| 6114000000-N | SP | 1.5 | HR | SPECIALIZED HAND MOWING |
| 6117000000-N | 1675 | 8 | EA | RESPONSE FOR EROSION CONTROL |

5/28/99

03-FEB-2005 08:54
p:\roadway\proj\164260sum.dgn
cpowell