

DIVISION OF HIGHWAYS
 STATE OF NORTH CAROLINA
SUMMARY OF EARTHWORK
 IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
SUMMARY #1					
-DET1- Sta. 10+00.00 TO 12+95.83	181		232	51	
-DET2- Sta. 10+00.00 TO 13+93.79	262		159		103
SUMMARY NO. 1 SUBTOTAL	443		391	51	103
SUMMARY #2					
-L1- Sta. 21+05.00 TO 23+37.00	13		79	66	
-L1- Sta. 23+82.00 TO 25+55.00	15		63	48	
-L2- Sta. 30+10.00 TO 32+63.00	51		48		3
-L2- Sta. 33+08.00 TO 34+00.00	46		3		43
-DRIVE1- Sta. 10+00.00 TO 10+61.09	7		2		5
-DRIVE2- Sta. 10+12.93 TO 10+70.50	111				111
SUMMARY NO. 2 SUBTOTAL	243		195	114	162
SUMMARY OF SUBTOTALS (1-2)	686		586	165	265
EST. SHOULDER CONSTRUCTION			87	87	
WASTE TO REPLACE BORROW				-252	-252
SUBTOTAL	686		673	0	13
DETOUR REMOVAL	898		449		449
SUBTOTAL	1,584		1,122		462
PROJECT SUBTOTAL	1,584		1,122		462
GRAND TOTAL	1,584		1,122		462
SAY	1,650				500

RIGHT OF WAY AREA DATA

PARCEL NO.	PROPERTY OWNERS NAMES	TOTAL ACREAGE	AREA TAKEN	AREA REMAINING RT.	AREA REMAINING LT.	CONST. EASE.	PERM. DRAIN. EASE.	TEMP. DRAIN. EASE.	TEMP. UTILITY EASE.	EXISTING RIGHT OF WAY
1	RAYMOND G. SWEET JR.	6.04 AC	0.13 AC		5.91 AC	0.14 AC			865 SF	0.07 AC
2	KENNETH T. WINEBARGER ESTATE	137.90 AC	0.33 AC	93.27 AC	44.30 AC		450.21 SF		4475 SF	0.23 AC
3	EDWARD & JOYCE PARSONS	4.99 AC	0.36 AC		4.63 AC	1853.09 SF				0.32 AC
4	REGINA PARSONS ALLEN	1.10 AC	0.13 AC		0.97 AC	333.22 SF				0.10 AC
5	MARY RUBY WILCOX	3.42 AC	0.16 AC	3.26 AC		2,742.54 SF	168.34 SF		3195 SF	0.11 AC
6	CHARLES & PATRICIA BINGHAM JR.	0.50 AC	0.08 AC	0.42 AC		4,212.22 SF	56.66 SF		1080 SF	0.05 AC
7	HAZEL WILSON	134,600.40 SF	389.57 SF		134,210.83 SF					0.00 AC
8	DARREN & LISA HODGES	0.83 AC	0.11 AC	0.72 AC	0.00 AC	2,577.65 SF				0.12 AC
9	PATRICIA ANN WRIGHT-GREEN	0.95 AC	0.00 AC	0.92 AC	0.03 AC	353.28 SF				0.26 AC

PAVEMENT REMOVAL IN SQUARE YARDS

LINE	LT/RT	STATION TO STATION	SQ. YDS
-DET1-	-CL-	10+00.00 TO 12+95.83	525.50
-DET2-	-CL-	10+00.00 TO 13+70.06	648.00
PROJECT TOTAL			1173.40
SAY			1200 SY

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, BORROW EXCAVATION, SHOULDER BORROW, FINE GRADING, CLEARING AND GRUBBING, BREAKING OF EXISTING PAVEMENT AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE LUMP SUM PRICE FOR "GRADING".

6/4/99
0127\05_154244
r:\Roadway\p\p\3926_rdy_sum.dgn