


5/28/09

PROJECT REFERENCE NO. B-3922	SHEET NO. 2
RW SHEET NO.	
ROADWAY DESIGN ENGINEER 	PAVEMENT DESIGN ENGINEER 


PAVEMENT SCHEDULE	
ITEM	DESCRIPTION
C1	PROP. APPROX. 2 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 137.5 LBS. PER SQ. YD. IN EACH OF TWO LAYERS
E1	PROP. APPROX. 4" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
J1	PROP. 8" CLASS A STONE (SEE DETAIL SHEET 2-A)
T	EARTH MATERIAL

NOTE: All Pavement Edge Slopes Are To Be 1:1.



USE TYPICAL SECTION No. 1  
 -L- STA. 10+08.34 TO 10+29.00 (Begin Bridge)  
 -L- STA. 11+84.00 (End Bridge) TO 12+11.59

0/4/19/2005 R:\Roadway\Proj\B3922\_P01\_TYP.DGN

**PLANS PREPARED BY :**  
 **RUMMEL • KLEPPER & KAHL, LLP**  
*consulting engineers*  
 5800 FARINGDON PLACE SUITE 105  
 RALEIGH, NORTH CAROLINA 27609-3960  
**FOR**  
**DIVISION OF HIGHWAYS**