PROJECT NO. : B-4327 COUNTY WILSON COMP. BY: JBT CHKD BY: ITY SHEET 1

LOCATION	EXCAVATION (CU. YDS.)				EMBANKMENT (CU. YDS.)				BORROW C.Y.	WASTE	
	TOTAL UNCL EXCA	EARTH SUITABLE			TOTAL EMBANKMENT		EARTH EMBANKMENT	EMBANKMENT PLUS 25%		C.Y. SUITABLE	C.Y. UNSUITABLE
SUMMARY NO. 1											
-L- 18+00 TO 23+15	262	262			2,115		2,115	2,644	2,382		
-L- 24+45 TO 30+50	97	97			8,331		8,331	10,414	10,317		
SUMMARY TOTAL	359	359			10,446		10,446	13,058	12,699		
EST. 5% TO Repl. Top Soil at Borr. Pit									635		
PROJECT TOTALS	359	359			10,446		10,446	13,058	13,333		
SAY:	**400**								**13,400**		
ESTIMATED UNDERCUT= 500 C.Y.											