

SUMMARY OF EARTHWORK
IN CUBIC YARDS

STATION TO STATION	UNCLASSIFIED EXCAVATION	EMBANKMENT + %	BORROW	WASTE
-L- STA. 11+00 TO -L- STA. 17+09	6352	9993	3641	0
-D3- STA. 10+10 TO -D3- STA. 11+50	121	2159	2038	0
-D3A- STA. 10+78.70 TO -D3A- STA. 11+20	4	66	62	0
SUBTOTAL 1	6477	12218	5741	0
-L- STA. 21+01 TO -L- STA. 26+50	35148	1414	0	33734
-D2- STA. 10+10 TO -D2- STA. 12+66.81	2778	2	0	2776
SUBTOTAL 2	37926	1416	0	36510
PROJECT SUBTOTAL	44403	13634	5741	36510
LOSS OF UNCLASSIFIED EXCAVATION DUE TO CLEARING & GRUBBING	-1300		1300	
SUBTOTAL	43103	13634	7041	36510
ROCK WASTE IN LIEU OF BORROW			-5875	-5875
ADJUSTMENT FOR ROCK WASTE		-881	-881	
SUITABLE WASTE IN LIEU OF BORROW			-285	-285
PROJECT TOTAL	43103	12753	0	30350
SAY	43500 CY			

EST. DDE = 45 CY
 EST. UNDERCUT = 300 CY

APPROXIMATE QUANTITIES ONLY. FINE GRADING AND CLEARING AND GRUBBING PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING".

SUMMARY OF SHOULDER BERM GUTTER
IN FEET

LOCATION	BEGINNING STATION	ENDING STATION	LENGTH
-L- RT	21+25.00	21+44.00	19
-L- LT	21+25.00	21+44.00	19
		TOTAL	38
		SAY	40

SUMMARY OF 4 STRAND BARBED WIRE FENCE W/POSTS
IN FEET

LOCATION	BEGINNING STATION	ENDING STATION	LENGTH
-L- RT	23+70	26+75	305
		TOTAL	305
		SAY	310