SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201223

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ********** (14+65.00-L-)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
0057000000-E	226	150	CY	UNDERCUT EXCAVATION
0134000000-E	240	20	CY	DRAINAGE DITCH EXCAVATION
0708000000-E	310	64	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	6	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
1220000000-E	545	50	TON	INCIDENTAL STONE BASE
1489000000-E	610	470	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1525000000-E	SP	212	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-E	620	34	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	25	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2286000000-N	840	3	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	3	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-E	846	280	LF	SHOULDER BERM GUTTER
3030000000-E	862	325	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3628000000-E	876	6	TON	PLAIN RIP RAP, CLASS I
3649000000-E	876	119	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	804	SY	FILTER FABRIC FOR DRAINAGE
4412000000-E	SP	424	SF	WORK ZONE SIGNS (STATIONARY)
4412200000-E	SP	144	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4446100000-E	SP	104	LF	BARRICADES (TYPE III)
4810000000-E	1205	5,640	LF	PAINT PAVEMENT MARKING LINES (4")
5300000000-E	1505	10	TON	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ******** (IV)
5306000000-E	SP	10	TON	BEDDING MATERIAL, UTILITIES CLASS ********** (IV)
5444000000-E	1510	93.5	LF	6" PVC WATER PIPE, SDR ******* (SDR 21, 200# WP)
5480000000-E	1510	200	LB	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP
5540000000-E	1510	2	EA	6" GATE VALVE & VALVE BOX, 200# WP
5888000000-E	SP	591	LF	GENERIC UTILITY ITEM 8" HDPE WATER PIPE, SDR 9, 200# WP BY DIRECTIONAL BORE
6000000000-E	1605	550	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	170	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	255	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	1.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
6024000000-E	1622	50	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	3	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6029000000-E	SP	250	LF	SAFETY FENCE
6030000000-E	1630	365	CY	SILT EXCAVATION
6036000000-E	1631	850	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	60	LF	1/4" HARDWARE CLOTH
6070000000-N	SP	8	EA	SPECIAL STILLING BASINS
6084000000-E	1660	1.5	ACR	SEEDING & MULCHING
6087000000-E	1660	1	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

8/17/99
18-FEB-2005 09:09
r:\roadway\proj\b3828_rdy_sht3.dgn
smeadows PT RH(2)2457