

B-3828**Project Special Provisions
Erosion Control****Cleveland County****Seeding And Mulching****(6)**

The kinds of seed and fertilizer, and the rates of application of seed, fertilizer, and limestone, shall be as stated below. During periods of overlapping dates, the kind of seed to be used shall be determined by the Engineer. All rates are in pounds per acre (kilograms per hectare).

August 1 - June 1

May 1 - September 1

100# (110kg) Tall Fescue	100# (110kg) Tall Fescue
15# (17kg) Kentucky Bluegrass	15# (17kg) Kentucky Bluegrass
15# (17kg) Hard Fescue	15# (17kg) Hard Fescue
500# (560kg) Fertilizer	25# (28kg) Kobe or Korean Lespedeza
4000# (4500kg) Limestone	500# (560kg) Fertilizer
	4000# (4500kg) Limestone

Approved Tall Fescue Cultivars:

Adventure	Adventure II	Amigo	Anthem
Apache	Apache II	Arid	Austin
Brookstone	Bonanza	Bonanza II	Chapel Hill
Chesapeake	Chieftain	Coronado	Crossfire II
Debutante	Duster	Falcon	Falcon II
Finelawn Petite	Finelawn	Finelawn I	Genesis
Grande	Guardian	Houndog	Jaguar
Jaguar III	Kentucky 31	Kitty Hawk	Monarch
Montauk	Mustang	Olympic	Pacer
Phoenix	Pixie	Pyramid	Rebel
Rebel Jr.	Rebel II	Renegade	Safari
Shenandoah	Tempo	Titan	Tomahawk
Trailblazer	Tribute	Vegas	Wolfpack
Wrangler			

Approved Kentucky Bluegrass Cultivars:

Adelphi	Baron	Bristol	Challenger
Columbia	Fylking	Glade	Kenblue
Merit	Plush	Ram I	Rugby
Sydsport	Touchdown	Vantage	

Approved Hard Fescue Cultivars:

Aurora	Bardur	Crystal	Reliant	Scaldis
Spartan	Valda	Waldina	Warwick	

On cut and fill slopes 2:1 or steeper add 25# (28kg) Rye Grain November 1 - March 1.

On cut and fill slopes 2:1 or steeper add 30# (35 kg) Sericea Lespedeza January 1 - December 31.

Fertilizer shall be 10-20-20 analysis. Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 1-2-2 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as a 10-20-20 analysis.

Temporary Seeding:

Fertilizer shall be the same analysis as specified for "Seeding and Mulching" and applied at the rate of 400 pounds (450kg) and seeded at the rate of 50 pounds per acre (55kg per hectare). Kobe or Korean Lespedeza, German Millet, or Browntop Millet shall be used in summer months and rye grain during the remainder of the year. The Engineer will determine the exact dates for using each kind of seed.

Fertilizer Topdressing:

Fertilizer used for topdressing shall be 16-8-8 grade and shall be applied at the rate of 500 pounds per acre (560 kg per hectare). Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 2-1-1 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as 16-8-8 analysis.

Supplemental Seeding:

The kinds of seed and proportions shall be the same as specified for "Seeding and Mulching", and the rate of application may vary from 25# to 75# per acre (28kg to 85kg per hectare). The actual rate per acre (hectare) will be determined by the Engineer prior to the time of topdressing and the Contractor will be notified in writing of the rate per acre (hectare), total quantity needed, and areas on which to apply the supplemental seed. Minimum tillage equipment, consisting of a sod seeder shall be used for incorporating seed into the soil as to prevent disturbance of existing vegetation. A clodbuster (ball and chain) may be used where degree of slope prevents the use of a sod seeder.

Mowing:

The minimum mowing height on this project shall be six inches (150 mm).

Specialized Hand Mowing:

The work covered by this section consists of specialized hand mowing around or under fixed objects, including but not limited to guardrails, signs, barriers and slopes in a method acceptable to the Engineer.

The work of specialized hand mowing shall be completed with mechanically powered trimmers, string trimmers, hand operated rotary mowers, or self-propelled mowers of sufficient size and quality to perform the work timely and efficiently.

The quantity of mowing to be performed will be affected by the actual conditions which occur during the construction of the project. The quantity of mowing may be increased, decreased or eliminated entirely at the direction of the Engineer. Such variations in quantity will not be considered as alterations in the details of construction or a change in the character of the work.

The quantity of specialized hand mowing to be paid for will be the actual number of man hours worked while hand mowing along the surface of the ground, at the direction of the Engineer. Where an area has been mowed more than once, at the direction of the Engineer, separate measurement will be made each time the area is mowed.

Payment will be made under:

Specialized Hand Mowing.....HR

Minimize Removal Of Vegetation

The Contractor shall minimize removal of vegetation at stream banks and disturbed areas within the project limits as directed by the Engineer.

Stockpile Areas

The Contractor shall install and maintain erosion control devices sufficient to contain sediment around any erodible material stockpile areas as directed by the Engineer.

Waste Areas And Borrow Sources:

Payment for temporary erosion control measures, except those made necessary by the Contractor's own negligence or for his own convenience, will be paid for at the appropriate contract unit price for the devices or measures utilized in borrow sources and waste areas.

No additional payment will be made for erosion control devices or permanent seeding and mulching in any commercial borrow or waste pit. All erosion and sediment control practices which may be required on a commercial borrow or waste site will be done at the Contractor's expense.

Temporary Diversion:

The work by this section for installation, maintenance, and cleanout of temporary diversions shall be in accordance with Section 1630. The quantity of excavation for installation and cleanout measured as provided in Article 1630-4 will be paid for at the contract unit price per cubic yard (cubic meter) as provided in Article 1630-5 for "Silt Excavation".

Safety Fence:

Description:

The work of "Safety Fence" shall consist of furnishing, installing and maintaining polyethylene or polypropylene fence along the outside riparian buffer, wetland, or water boundary located within the construction corridor to mark the areas that have been approved to infringe within the buffer, wetland or water, and as directed by the Engineer in accordance with the special provisions included herein. The fence shall be installed prior to any land disturbing activities.

Materials:

Fence Material:

Polyethylene or polypropylene fence shall be a preconstructed safety fence approved by the Engineer.

Posts:

Either wood posts or steel posts may be used. Wood posts shall be nominal 2" x 4" (51 mm x 102 mm) or 4" x 4" (102 mm x 102 mm), lengths as required, structural light framing, grade No. 2, Southern Pine. Steel posts shall be at least 5 feet (1.6 m) in length, approximately 1 3/8" (35 mm) wide measured parallel to the fence, and have a minimum weight of 1.25 lb./ft. (1.9 kg/m) of length. The steel post shall be equipped with an anchor plate having a minimum area of 14 square inches (90 square centimeters).

Clearing and Grading:

No additional clearing and grubbing is anticipated for the installation of this fence; however, if any clearing and grubbing is required, it will be the minimum required for the installation of the safety fence. Such clearing shall include satisfactory removal and disposal of all trees, brush, stumps and other objectionable material.

The fence shall be erected to conform to the general contour of the ground. When determined necessary by the Engineer, minor grading along the fence line shall be done to meet this requirement provided no obstructions to proper drainage are created.

Installation:

Posts shall be set and maintained in a vertical position and may be hand set or set with a post driver. If hand set, all backfill material shall be thoroughly tamped. If power driven, wood posts may be sharpened to a dull point. Posts damaged by power driving shall be removed and replaced prior to final acceptance. The tops of all wood posts shall be cut at a 30 degree angle. The wood posts may, at the option of the Contractor, be cut at this angle either before or after the posts are erected.

The fence fabric shall be attached to the wood posts with one 2" (51 mm) galvanized wire staple across each cable or to the steel posts with wire or other acceptable means.

The Contractor shall be required to maintain the safety fence in a satisfactory condition for the duration of the project as determined by the Engineer.

Method of Measurement:

The quantity of safety fence to be paid for shall be the actual number of linear feet (meter) of "Safety Fence", installed in place and accepted. No direct payment will be made for post and post bracing. Cost shall be included in the cost of the fence per linear foot (meter).

Basis of Payment:

The quantity of safety fence measured as provided above will be paid for at the contract unit price per linear foot (meter) of safety fence. Such payment will be full compensation for the work as described in the above paragraphs, including but not limited to clearing and grading, furnishing and installing fence fabric with necessary posts and post bracing, staples, tie wires, tools, equipment and incidentals necessary to complete the work.

Payment will be made under:

Safety Fence.....LF (M)

Gravel Construction Entrance:

Description:

The work covered by this section consists of furnishing, installing, and maintaining and removing any and all material required for the construction of a Gravel Construction Entrance.

Materials:

The filter fabric shall meet the requirements of Section 1056 for Type 2 Fabric.

Stone shall be Class A Stone and shall meet the requirements of Section 1042 for Stone for Erosion Control, Class A.

Construction:

The Contractor shall install a Gravel Construction Entrance in accordance with the details in the plans and at locations as directed by the Engineer.

Method Of Measurement:

Gravel Construction Entrance will not be measured for payment under this section.

Basis Of Payment:

Payment for installation of Filter Fabric shall be paid for at the contract unit price per square yard (square meter) "Filter Fabric for Drainage".

Payment for installation of Class A Stone shall be paid for at the contract unit price per ton (metric ton) "Stone for Erosion Control, Class A".

Such price and payment shall be considered full compensation for all work covered by this provision including all materials, construction, maintenance, and removal of Gravel Construction Entrance as directed by the Engineer.

Special Stilling Basin(s):**Description:**

The work covered by this section consists of furnishing, placing, and removing a special stilling basin(s) as directed by the Engineer. The special stilling basin(s) shall be used to filter pumped water during construction of drilled piers.

Materials:

The filter fabric shall meet the requirements of Section 1056 for Type 2 Fabric.

Sediment control stone shall meet the requirements of Section 1005. Install stone according to the detail shown on the plans.

The special stilling basin(s) shall be a water permeable fabric bag that traps sand, silt, and fines as sediment laden water is pumped into it. This device shall be constructed such that it is portable and can be used adjacent to each drilled pier.

The special stilling basin(s) shall be a bag constructed to a minimum size of 10' x 15' made from a nonwoven fabric. It shall have a sewn-in 8 in. (maximum) spout for receiving pump discharge. The bag seams shall be sewn with a double needle machine using a high strength thread. The seams shall have a minimum wide width strength as follows:

Test Method	Minimum Specifications
ASTM D-4884	60 lb/in

The fabric used to construct the bag shall be stabilized to provide resistance to ultra-violet degradation and meet the following specifications for flow rates, strength, and permeability:

Property	Test Method	Units	Minimum Specifications
Weight	ASTM D-3776	oz/yd	8.0
Grab tensile	ASTM D-4632	lb	200.0
Puncture	ASTM D-4833	lb	130.0
Flow rate	ASTM D-4491	gal/min/sf	80.0
Permittivity	ASTM D-4991	1/sec	1.5
UV Resistance	ASTM D-4355	%	70.0

Construction:

The Contractor shall install the special stilling basin in accordance with the details in the plans and at locations as directed by the Engineer.

The special stilling basin(s) shall be placed so the incoming water flows into and through the bag without causing erosion. The neck or spout of the bag shall be tied off tightly to stop the water from flowing out of the bag without going through the walls.

The special stilling basin(s) shall be replaced and disposed of when it is 3/4 full of sediment or when it is impractical for the bag to filter the sediment out at a reasonable flow rate. Prior approval from the Engineer must be received before removal and replacement.

The Contractor shall be responsible for providing a sufficient quantity of bags to contain silt from pumped effluent during construction of drilled piers.

Method Of Measurement:

The quantity of special stilling basin(s) to be paid for will be the actual number of bags used during drilled pier construction as specified and accepted by the Engineer.

Measurement of filter fabric will be made by the number of square yards (square meters) as measured over the surface of the ground over which filter fabric has been acceptably placed.

The quantity of sediment control stone will be measured according to Article 1610-4.

Basis Of Payment:

Payment for special stilling basin will be as follows:

Filter Fabric for Drainage	SY(SM)
Sediment Control Stone	TON (MT)
Special Stilling Basin	EA

Such price and payment will be full compensation for all work covered by this provision, including but not limited to, furnishing all materials, placing and maintaining the special stilling basin(s), and removal and disposal of silt accumulations and bag.