

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	500 CY		
0006	0036000000-E	225	UNDERCUT EXCAVATION	7,100 CY		
0007	0106000000-E	230	BORROW EXCAVATION	15,600 CY		
0008	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	1,100 SY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	1,500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,300 SY		
0011	0206000000-E	SP	TEMPORARY SHORING - BARRIER SUPPORTED	2,540 SF		
0012	0241000000-E	SP	GENERIC GRADING ITEM ROCK PLATING	750 SY		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	112 LF		
0014	0546000000-E	310	*** CAA PIPE CULVERTS, ***** THICK (36", 0.075")	320 LF		
0015	0995000000-E	340	PIPE REMOVAL	80 LF		
0016	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0017	1121000000-E	520	AGGREGATE BASE COURSE	260 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	600 TON		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	520 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	60 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	30 TON		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	290 LF		
0025	3030000000-E	862	STEEL BM GUARDRAIL	625 LF		
0026	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0028	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0029	3649000000-E	876	PLAIN RIP RAP, CLASS B	5 TON		
0030	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	160 SY		
0031	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	148 SF		
0032	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	365 SF		
0033	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	70 SF		
0034	4425000000-N	1125	WARNING FLAG SETS	4 EA		
0035	4430000000-N	1130	DRUMS	50 EA		
0036	4435000000-N	1135	CONES	30 EA		
0037	4446100000-E	SP	BARRICADES (TYPE III)	80 LF		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4455000000-N	1150	FLAGGER	16		MD
0039	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4		EA
0040	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	4		EA
0041	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	2		EA
0042	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,580		LF
0043	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	1,140		LF
0044	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,896		LF
0045	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,896		LF
0046	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	10,850		LF
0047	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	37		LF
0048	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	400		LF
0049	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	34		EA
0050	6000000000-E	1605	TEMPORARY SILT FENCE	985		LF
0051	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75		TON
0052	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	155		TON
0053	6012000000-E	1610	SEDIMENT CONTROL STONE	300		TON
0054	6015000000-E	1615	TEMPORARY MULCHING	0.5		ACR
0055	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50		LB

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25	TON	
0057	6029000000-E	SP	SAFETY FENCE	300	LF	
0058	6030000000-E	1630	SILT EXCAVATION	370	CY	
0059	6036000000-E	1631	MATTING FOR EROSION CONTROL	525	SY	
0060	6042000000-E	1632	1/4" HARDWARE CLOTH	835	LF	
0061	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	107	SY	
0062	6084000000-E	1660	SEEDING & MULCHING	0.5	ACR	
0063	6087000000-E	1660	MOWING	0.5	ACR	
0064	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0065	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0066	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0067	6108000000-E	1665	FERTILIZER TOPDRESSING	1	TON	
0068	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0069	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8	EA	
0070	7060000000-E	1705	SIGNAL CABLE	1,300	LF	
0071	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	4	EA	
0072	7252000000-E	1710	MESSENGER CABLE (1/4")	70	LF	
0073	7264000000-E	1710	MESSENGER CABLE (3/8")	1,180	LF	
0074	7300000000-E	1715	TRENCHING (UNPAVED)	80	LF	
0075	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	2	EA	

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	7360000000-N	1720	WOOD POLE	8 EA		
0077	7372000000-N	1721	GUY ASSEMBLY	4 EA		
0078	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0079	7420000000-E	1722	2" RISER WITH WEATHERHEAD	4 EA		
0080	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	400 LF		
0081	7456000000-E	1726	LEAD-IN CABLE	1,320 LF		
0082	7636000000-N	1745	SIGN FOR SIGNALS	2 EA		
0083	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
0084	7780000000-N	SP	DETECTOR CARD (TYPE 2070L)	1 EA		
<b>STRUCTURE ITEMS</b>						
0085	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (24+18.00-L-)	Lump Sum	L.S.	
0086	8112700000-N	SP	DYNAMIC LOAD TEST	3 EA		
0087	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (24+18.00-L-)	Lump Sum	L.S.	
0088	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	107.1 CY		
0089	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (24+18.00-L-)	Lump Sum	L.S.	
0090	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	17,392 LB		
0091	8333000000-E	450	16" PRESTRESSED CONC PILES	1,585 LF		
0092	8350000000-E	450	24" PRESTRESSED CONC PILES	1,530 LF		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	8398000000-N	SP	STEEL PILE TIPS	18 EA		
0094	8475000000-E	460	TWO BAR METAL RAIL	339.33 LF		
0095	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-8 1/2")	355.22 LF		
0096	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	185 TON		
0097	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	215 SY		
0098	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0099	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	3,012.38 LF		
0100	8860000000-N	SP	GENERIC STRUCTURE ITEM EPOXY SAND SURFACE	Lump Sum	L.S.	
0101	8860000000-N	SP	GENERIC STRUCTURE ITEM RAILING SYSTEM	Lump Sum	L.S.	
0102	8874000000-E	SP	GENERIC STRUCTURE ITEM SCOUR PROTECTION STONE	20 TON		
0758/Apr14/Q87043.83/D509444600000/E102			Total Amount Of Bid For Entire Project :			

C200858 (B-3445)  
COUNTY: Currituck County

2/16/99

Contract No: C200858  
County: Currituck

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General

Signature Sheet (Bid - Acceptance by Department)