

## LEGEND SUPPLEMENT

In addition to the terms and abbreviations listed on the Legend Sheet, the following will be used to further describe rock quality on this project. Because of limited space on the logs, abbreviations are in parenthesis.

### WEATHERING

Fresh	Rock fresh, crystals bright, few joints may show slight staining. Rock rings under hammer in crystalline.
Very Slight (V. SLI.)	Rock generally fresh, joints stained, some joints may show thin clay coatings if open, crystals on a broken specimen face shine brightly. Rock rings under hammer blows if of a crystalline nature.
Slight (SLI.)	Rock generally fresh, joints stained and discoloration extends into rock up to 0.025 m (1 in.). Open joints may contain clay. In granitoid rocks some occasional feldspar crystals are dull and discolored.
Moderate (MOD.)	Significant portions of rock show discoloration and weathering effects. In granitoid rocks, most feldspars are dull and discolored, some show clay. Rock has dull sound under hammer blows and
Moderately Severe (MOD. SEV.)	All rock except quartz discolored or stained. In granitoid rocks, all feldspars dull and discolored and a majority show kaolinization. Rock shows severe loss of strength & can be excavated with geologist's pick. Rock gives "clunk" sound when struck. <u>Comparable to hard weathered rock.</u>
Severe (SEV.)	All rocks except quartz discolored or stained. Rock "fabric" clear and evident but reduced in strength to strong soil. In granitoid rocks all feldspars are kaolinized to some extent. Some fragments of <u>Comparable to soft weathered rock.</u>
Very Severe (V. SEV.)	All rock except quartz discolored or stained. Rock fabric elements are discernible but the mass is effectively reduced to soil status, with only fragments of strong rock remaining. Saprolite is an <u>Comparable to soil.</u>
Complete	Rock reduced to soil. Rock fabric not discernible only in small and scattered concentrations. Quartz <u>Comparable to soil.</u>

### ROCK CONTINUITY

Sound	Core pieces larger than 0.20 m.
Slightly Fractured (SLI. FRAC.)-	Core pieces between 0.10 m and 0.20m.
Moderately Fractured (MOD. FRAC.)-	Core pieces between 0.025 m and 0.10 m.
Extremely Fractured (EXT. FRAC.)-	Core pieces less than 0.025 m.

### JOINT SPACING

Average Discontinuity Spacing (ADS)

The average measured distance (in meters) between joints in the same set. Will not apply to individual joints.

### JOINT THICKNESS

Average Discontinuity Thickness (ADT)

The average thickness or width of gap in the joint (in meters).