METRIC	PROJECT REFERENCE NO.	SHEET NO.
-5 0 10	R-2552B	40A
	ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
	PRELIMINARY PLANS DO NOT USE FOR CONSTRUCTION	
CONST.REV. _____		
R/W REV. _____		

SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	PL. I.	% BY WEIGHT				% PASSING SIEVES			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
SS-179	CL	1+20	0.83-1.28	A-7-5(15)	53	21	6.9	25.5	15.1	52.6	95	92	69	22.9	
SS-180	CL	1+20	2.35-2.80	A-7-5(18)	69	16	7.3	23.1	49.4	20.2	100	95	76	41.4	
ST-7	CL	1+20	2.50-2.92	A-7-5(19)	74	24	8.4	34.8	34.3	22.5	100	96	66		
ST-8	CL	1+20	3.11-3.72	A-7-5(14)	66	14	7.3	28.1	44.4	20.2	100	96	71		
S-181	CL	2+00	0.10-0.80	A-6(6)	40	17	14.0	28.3	17.3	40.4	80	73	51		
S-322	CL	2+80	0.00-1.15	A-7-5(29)	74	25	1.6	17.0	28.8	52.6	100	99	85		
S-323	CL	2+80	2.50-2.80	A-7-5(27)	67	31	3.0	24.9	29.6	42.5	100	99	76		
SS-324	CL	3+40	1.08-1.53	A-7-5(27)	66	31	6.7	16.8	13.7	62.8	100	97	78	30.7	
SS-325	CL	3+40	2.60-3.05	A-7-5(10)	55	14	10.7	28.8	34.1	26.3	100	97	65	28.4	
SS-326	CL	3+40	5.64-6.09	A-7-5(11)	50	13	4.1	30.6	43.1	22.3	100	99	72		
SS-327	CL	3+40	8.68-9.13	A-5(3)	43	10	13.0	44.6	32.3	10.1	100	97	49	32.7	
SS-316	CL	1+40	0.00-0.45	A-7-6(9)	43	21	15.4	29.3	12.8	42.5	96	86	57		
SS-317	CL	1+40	0.70-1.15	A-7-5(22)	62	26	7.3	22.4	15.7	54.6	100	96	75	29.2	
SS-318	CL	1+40	3.74-4.19	A-7-5(21)	84	22	5.1	22.9	33.7	38.4	90	88	69	63.7	
SS-319	CL	1+40	5.76-5.71	A-5(6)	48	9	3.2	38.2	38.3	20.2	100	99	64		

$$$$SYSTIME$$$$
$$$$$$$$DGN$$ $$$$$$$$$$
$$$$USERNAME$$$$