



- (A) COASTAL PLAIN, ORANGE AND WHITE, VERY SOFT, WET, SANDY CLAY
- (B) COASTAL PLAIN, BROWN-GRAY, LOOSE TO MEDIUM DENSE, MOIST, SILTY SAND

**SOIL TEST RESULTS**

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.L. I.	% BY WEIGHT				% PASSING SIEVES		
							C. SAND	F. SAND	SILT	CLAY	10	40	200
S-206	0	121+20	0.65-1.10	A-7-6(11)	51	25	27.7	12.9	11.2	48.2	89	73	55
S-207	0	121+20	1.90-2.35	A-2-7(4)	50	28	48.6	14.7	4.6	32.1	91	62	35
S-208	0	121+20	5.50-5.90	A-2-7(2)	48	27	54.7	13.7	5.5	26.1	83	48	28
S-209	0	121+20	7.30-7.70	A-2-7(2)	55	29	60.6	12.1	6.1	21.1	85	43	24
S-213	14	122+39	4.17-4.62	A-2-7(5)	63	38	59.2	8.4	6.3	26.1	98	51	32
S-214	14	122+39	7.21-7.66	A-7-6(3)	41	21	40.1	28.1	11.7	20.1	89	58	38
S-215	14	122+39	8.73-9.18	A-1-b(0)	33	NP	76.2	7.6	8.1	8.0	99	38	17
S-216	14	122+39	11.77-12.22	A-7-6(17)	45	19	2.4	42.3	17.2	38.1	100	98	82
S-217	14	122+39	17.85-18.30	A-2-4(0)	28	7	29.5	38.5	20.0	12.0	69	58	26
S-218	14	122+39	19.37-19.82	A-4(0)	29	6	26.3	36.1	19.6	18.1	89	79	39
S-219	-8	123+00	1.70-2.00	A-6(4)	39	16	34.9	22.9	10.1	32.1	100	82	45
S-220	-8	123+00	3.40-3.70	A-2-4(0)	18	NP	49.9	36.9	11.1	2.0	99	73	18
S-221	-8	123+00	6.60-7.00	A-2-6(1)	39	23	55.6	19.1	7.3	18.1	96	58	26