

Calc by TAM Checked by BKE

PROJECT			8.T311002 (R-2552C)				COUNTY			JOHNSTON		SHEET		2		3	
LINE	STATION	STATION	TOTAL EXCAV. (UNCL.)	ROCK EXCAV.	UNDERCUT EXCAV.	UNSUIT EXCAV.	SUITABLE EXCAV.	TOTAL EMB.	ROCK EMB.	EARTH EMB.	EMB +20%	BORROW	ROCK WASTE	SUITABLE EARTH WASTE	UNSUIT EARTH WASTE	TOTAL WASTE	
SUMMARY #7																	
-L2-	145+00.000	158+55.000	4,791				4,791	30,216		30,216	36,259	31,468		0	0	0	
-FLYOVER-	9+80.000	15+19.000	0				0	180,034		180,034	216,041	216,041		0	0	0	
-Y4-	17+00.000	23+80.000	1,901			827	1,074	73,800		73,800	88,560	87,486		0	827	827	
-Y4-	24+20.000	32+20.000	2,580				2,580	34,521		34,521	41,425	38,845		0	0	0	
-Y4A-	26+79.780	29+21.479	37				37	220		220	264	227		0	0	0	
-Y4A-		REMOVAL	220				220	37		37	44	0		176	0	176	
-Y4B-	39+00.000	40+40.000	0				0	44		44	53	53		0	0	0	
-Y4B-		REMOVAL	44				44	0		0	0	0		44	0	44	
-Y4DET-	24+80.000	28+80.000	491				491	2,131		2,131	2,557	2,066		0	0	0	
-Y4DET-		REMOVAL	2,131				2,131	491		491	589	0		1,542	0	1,542	
-RAMPA-	0+00.000	11+37.000	9,316		4,353	5,605	3,711	20,354		20,354	24,425	20,714		0	9,958	9,958	
-RAMPD-	0+00.000	4+20.000	8,583				8,583	1,560		1,560	1,872	0		6,711	0	6,711	
-Y7-	10+40.000	12+30.000	132				132	544		544	653	521		0	0	0	
		SUBTOTAL	30,226	0	4,353	6,432	23,794	343,952		343,952	412,742	397,421		8,473	10,785	19,258	
SUMMARY #8																	
-Y4-	5+80.000	17+00.000	8,045		235		8,045	20,709		20,709	24,851	16,806		0	235	235	
-Y5-	10+20.000	24+20.000	6,790		2,647	6,611	179	18,435		18,435	22,122	21,943		0	9,258	9,258	
-Y6-	10+20.000	15+60.000	130				130	10,692		10,692	12,830	12,700		0	0	0	
		SUBTOTAL	14,965	0	2,882	6,611	8,354	49,836		49,836	59,803	51,449	0	0	9,493	9,493	