

County : Greene, Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (19+21.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	11 TON		
0009	0343000000-E	310	15" SIDE DRAIN PIPE	48 LF		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	48 LF		
0011	0995000000-E	340	PIPE REMOVAL	38 LF		
0012	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,600 TON		
0014	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,300 TON		
0015	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,700 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	592 TON		
0017	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	110 TON		
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0020	2556000000-E	846	SHOULDER BERM GUTTER	240 LF		
0021	2612000000-E	848	6" CONCRETE DRIVEWAY	48 SY		
0022	3030000000-E	862	STEEL BM GUARDRAIL	612.5 LF		
0023	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0024	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0025	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0026	3649000000-E	876	PLAIN RIP RAP, CLASS B	23 TON		
0027	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	281 SY		
0028	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	93 LF		
0029	4082000000-E	903	SUPPORTS, WOOD	40 LF		
0030	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0031	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0032	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	1 EA		
0033	4129000000-N	906	RELOCATE SIGN, TYPE ***** (E)	2 EA		
0034	4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	2 EA		
0035	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	16 EA		
0036	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	20 SF		
0037	4446100000-E	SP	BARRICADES (TYPE III)	80 LF		

County : Greene, Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,150 LF		
0039	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,150 LF		
0040	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,600 LF		
0041	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	15 EA		
0042	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	30 TON		
0043	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	30 TON		
0044	5426000000-E	1510	**** PVC WATER PIPE, SDR ***** (3", SDR21)	564 LF		
0045	5480000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	250 LB		
0046	5534000000-E	1510	*** GATE VALVE & VALVE BOX, *****WP (3", 200 PSI)	2 EA		
0047	5600000000-E	SP	*** BLOW OFF ASSEMBLY (2")	1 EA		
0048	5888000000-E	SP	GENERIC UTILITY ITEM 4" HDPE WATER PIPE, BY DIRECTIONAL BORE	545 LF		
0049	6000000000-E	1605	TEMPORARY SILT FENCE	1,175 LF		
0050	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
0051	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	65 TON		
0052	6012000000-E	1610	SEDIMENT CONTROL STONE	50 TON		
0053	6015000000-E	1615	TEMPORARY MULCHING	3.5 ACR		

County : Greene, Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0055	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0056	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0057	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0058	6029000000-E	SP	SAFETY FENCE	300 LF		
0059	6030000000-E	1630	SILT EXCAVATION	150 CY		
0060	6036000000-E	1631	MATTING FOR EROSION CONTROL	400 SY		
0061	6070000000-N	SP	SPECIAL STILLING BASINS	2 EA		
0062	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0063	6087000000-E	1660	MOWING	2 ACR		
0064	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0065	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0066	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0067	6108000000-E	1665	FERTILIZER TOPDRESSING	2.5 TON		
0068	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0069	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
STRUCTURE ITEMS						
0070	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19+21.50 -L-)	Lump Sum	L.S.	

County : Greene, Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (19+21.50 -L-)	Lump Sum	L.S.	
0072	8161000000-E	420	GROOVING BRIDGE FLOORS	4,736 SF		
0073	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	36.4 CY		
0074	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19+21.50 -L-)	Lump Sum	L.S.	
0075	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,980 LB		
0076	8329000000-E	450	12" PRESTRESSED CONC PILES	900 LF		
0077	8503000000-E	460	CONCRETE BARRIER RAIL	145.5 LF		
0078	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	181 TON		
0079	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	201 SY		
0080	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0081	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0082	8753000000-E	SP	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	1,091.25 LF		
0083	8892000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE WEARING SURFACE	3,043 SF		
1348/Apr06/Q47654.9/D385597800000/E83			Total Amount Of Bid For Entire Project :			

C201200 (B-3866)
COUNTIES: GREENE & LENOIR

2/16/99

Contract No: C201200
County: Greene & Lenoir

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)