

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0004	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0005	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	275 TON		
0007	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	392 LF		
0008	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,214 LF		
0009	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	188 LF		
001C	0762000000-E	310	66" BIT COAT CS PIPE CULVERTS, TYPE B 0.138" THICK	364 LF		
0011	0774000000-E	310	78" BIT COAT CS PIPE CULVERTS, TYPE B 0.168" THICK	378 LF		
0012	0995000000-E	340	PIPE REMOVAL	203 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,800 TON		
0015	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,220 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,370 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	458 TON		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2000000000-N	806	RIGHT OF WAY MARKERS	28 EA		
0019	2022000000-E	815	SUBDRAIN EXCAVATION	224 CY		
002C	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0025	2220000000-E	838	REINFORCED ENDWALLS	40 CY		
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	20 EA		
0027	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	4 EA		
0028	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0029	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	10 EA		
003C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	4 EA		
0031	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0032	2440000000-N	840	CONCRETE APRON FOR CATCH BASIN	2 EA		
0033	2451000000-N	840	CONCRETE APRON FOR DROP INLETS	2 EA		
0034	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	2,650 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	4,950 LF		
0036	2591000000-E	848	4" CONCRETE SIDEWALK	2,550 SY		
0037	2598000000-E	848	CONCRETE WHEELCHAIR RAMPS	110 SY		
0038	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	135 SY		
0039	3649000000-E	876	PLAIN RIP RAP, CLASS B	14 TON		
0040	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	45 SY		
0041	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	168 SF		
0042	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	30 SF		
0043	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	96 SF		
0044	4430000000-N	1130	DRUMS	50 EA		
0045	4446100000-E	SP	BARRICADES (TYPE III)	100 LF		
0046	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,550 LF		
0047	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	350 LF		
0048	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	75 LF		
0049	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	16 EA		
0050	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	19 EA		
0051	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,750 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	482000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	350 LF		
0053	483500000-E	1205	PAINT PAVEMENT MARKING LINES (24")	75 LF		
0054	484000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	8 EA		
0055	484500000-N	1205	PAINT PAVEMENT MARKING SYMBOL	13 EA		
0056	600000000-E	1605	TEMPORARY SILT FENCE	3,000 LF		
0057	600900000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100 TON		
0058	601200000-E	1610	SEDIMENT CONTROL STONE	100 TON		
0059	601500000-E	1615	TEMPORARY MULCHING	2 ACR		
006C	601800000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0061	602100000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1 TON		
0062	603000000-E	1630	SILT EXCAVATION	50 CY		
0063	603600000-E	1631	MATTING FOR EROSION CONTROL	500 SY		
0064	604200000-E	1632	1/4" HARDWARE CLOTH	250 LF		
0065	608400000-E	1660	SEEDING & MULCHING	4.25 ACR		
0066	609000000-E	1661	SEED FOR REPAIR SEEDING	200 LB		
0067	609300000-E	1661	FERTILIZER FOR REPAIR SEEDING	1 TON		

C201440 (U-4737)
COUNTY: Pitt County

2/16/99

Contract No: C201440
County: Pitt

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General