

## SUMMARY OF EARTHWORK

IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	EMBT + %	BORROW
-L- 13+05.00 TO 16+30.00	29	1723	1694
-L- 17+40.00 TO 21+65.00	99	5569	5470
<b>PROJECT TOTALS</b>	<b>128</b>	<b>7292</b>	<b>7164</b>
EST. 5% TO REPLACE TOPSOIL ON BORROW PITS			358
<b>GRAND TOTAL</b>	<b>128</b>		<b>7522</b>
SAY	150		7600

UNDERCUT EXCAVATION = 200 C.Y.  
 DRAINAGE DITCH EXCAVATION = 900 C.Y.  
 PAVEMENT VOLUME = 31 C.Y.

NOTE:  
 APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION,  
 FINE GRADING, CLEARING AND GRUBBING, BREAKING OF  
 EXISTING PAVEMENT, AND REMOVAL OF EXISTING PAVEMENT WILL  
 BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING".

## SUMMARY OF PAVEMENT REMOVAL AND PAVEMENT BREAKUP

IN SQUARE YARDS

LINE	BEGIN STATION	END STATION	LOCATION	ASPHALT PAVEMENT REMOVAL	ASPHALT PAVEMENT BREAKUP
-L-	13+05.00	16+43.00	LT & RT	757	
-L-	17+23.00	17+64.00	LT & RT	84	
-L-	20+45.00	21+65.00	LT & RT	279	
-L-	17+64.00	20+45.00	LT & RT		625
			TOTAL	1120	625
			SAY	1150	650