

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
**SUMMARY OF QUANTITIES**

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201324

ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION
000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+85.00)
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
005700000-E	226	200	CY	UNDERCUT EXCAVATION
006300000-N	SP	Lump Sum		GRADING
010600000-E	230	7,600	CY	BORROW EXCAVATION
013400000-E	240	900	CY	DRAINAGE DITCH EXCAVATION
019500000-E	265	100	CY	SELECT GRANULAR MATERIAL
019600000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION
031800000-E	300	25	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
036600000-E	310	152	LF	15" RC PIPE CULVERTS, CLASS III
070800000-E	310	56	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
071400000-E	310	24	LF	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
080600000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
080700000-E	310	2	EA	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
148900000-E	610	500	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
149800000-E	610	300	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE H9.0B
152500000-E	SP	400	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
156000000-E	620	62	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
228600000-N	840	5	EA	MASONRY DRAINAGE STRUCTURES
236700000-N	840	5	EA	FRAME WITH TWO GRATES, STD 840.29
255600000-E	846	450	LF	SHOULDER BERM GUTTER

ItemNumber	Sec #	Quantity	Unit	Description
303000000-E	862	425	LF	STEEL BM GUARDRAIL
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
362800000-E	876	105	TON	PLAIN RIP RAP, CLASS I
364900000-E	876	260	TON	PLAIN RIP RAP, CLASS B
365600000-E	876	1,100	SY	FILTER FABRIC FOR DRAINAGE
441200000-E	SP	490	SF	WORK ZONE SIGNS (STATIONARY)
441220000-E	SP	148	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
442500000-N	1125	4	EA	WARNING FLAG SETS
444610000-E	SP	112	LF	BARRICADES (TYPE III)
481000000-E	1205	6,880	LF	PAINT PAVEMENT MARKING LINES (4")
600000000-E	1605	760	LF	TEMPORARY SILT FENCE
600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	220	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	95	TON	SEDIMENT CONTROL STONE
601500000-E	1615	1.5	ACR	TEMPORARY MULCHING
601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
602400000-E	1622	150	LF	TEMPORARY SLOPE DRAINS
602700000-N	1622	4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
602900000-E	SP	300	LF	SAFETY FENCE
603000000-E	1630	1,655	CY	SILT EXCAVATION
603600000-E	1631	950	SY	MATting FOR EROSION CONTROL
604200000-E	1632	100	LF	1/4" HARDWARE CLOTH
608400000-E	1660	2	ACR	SEEDING & MULCHING

ItemNumber	Sec #	Quantity	Unit	Description
608700000-E	1660	1	ACR	MOWING
609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	1.5	TON	FERTILIZER TOPDRESSING
611400000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

5/28/99

04-FEB-2005 16:15  
I:\Roadway\proj\B3700.sum  
T:\Walters