R:\Roadway\XSC\ear_l.log

PROJ. REFERENCE NO.	SHEET NO.
B-3700	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+05.00	0	0
13+50.00	8	62
14+00.00	13	160
14+50.00	6	182
15+00.00	2	203
15+50.00	0	262
16+00.00	0	333
16+30.00	0	234

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
17+40.00	0	60
17+50.00	0	162
18+00.00	0	868
18+50.00	0	934
19+00.00	0	845
19+50.00	13	649
20+00.00	19	451
20+50.00	10	331
21+00.00	7	232
21+50.00	39	102
21+65.00	11	7