

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+85.00)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	7,600 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	900 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	25 TON		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	152 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	56 LF		
0014	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0015	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0016	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	2 EA		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	500 TON		
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	300 TON		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	400 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	62 TON		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0022	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	5 EA		
0023	2556000000-E	846	SHOULDER BERM GUTTER	450 LF		
0024	3030000000-E	862	STEEL BM GUARDRAIL	425 LF		
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0026	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0028	3628000000-E	876	PLAIN RIP RAP, CLASS I	105 TON		
0029	3649000000-E	876	PLAIN RIP RAP, CLASS B	260 TON		
0030	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,100 SY		
0031	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	490 SF		
0032	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	148 SF		
0033	4425000000-N	1125	WARNING FLAG SETS	4 EA		
0034	4446100000-E	SP	BARRICADES (TYPE III)	112 LF		
0035	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,880 LF		
0036	6000000000-E	1605	TEMPORARY SILT FENCE	760 LF		
0037	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	220 TON		
0039	6012000000-E	1610	SEDIMENT CONTROL STONE	95 TON		
0040	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0041	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0042	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0043	6024000000-E	1622	TEMPORARY SLOPE DRAINS	150 LF		
0044	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0045	6029000000-E	SP	SAFETY FENCE	300 LF		
0046	6030000000-E	1630	SILT EXCAVATION	1,655 CY		
0047	6036000000-E	1631	MATTING FOR EROSION CONTROL	950 SY		
0048	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		
0049	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0050	6087000000-E	1660	MOWING	1 ACR		
0051	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0052	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0053	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0054	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0055	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5 HR		
0056	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0057	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (16+85.00 -L-)	Lump Sum	L.S.	
0058	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+85.00 -L-)	Lump Sum	L.S.	
0059	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16+85.00 -L-)	Lump Sum	L.S.	
0060	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	76.9 CY		
0061	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+85.00 -L-)	Lump Sum	L.S.	
0062	8217000000-E	425	REINFORCING STEEL (BRIDGE)	8,736 LB		
0063	8256000000-E	SP	TYPE III PRESRESSED CONCRETE DECK GIRDER	536.67 LF		
0064	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	4,200 LS		
0065	8364000000-E	450	HP12X53 STEEL PILES	270 LF		
0066	8391000000-N	450	STEEL PILE POINTS	9 EA		
0067	8468000000-E	460	ONE BAR METAL RAIL	199.67 LF		
0068	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-0" X 2'-1")	214.67 LF		
0069	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	662 TON		
0070	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	736 SY		
0071	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

C201324 (B-3700)
COUNTY: Stanly County

2/16/99

Contract No: C201324
County: Stanly

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)