

DIVISION OF HIGHWAYS  
 STATE OF NORTH CAROLINA

**DOUBLE FACE CABLE GUIDERAIL SUMMARY**

SURVEY LINE	BEG. STATION	END STATION	LOCATION	LENGTH	TOTAL GUIDERAIL LENGTH (LENGTH PLUS 15.2m FOR INTERMEDIATE ANCHORAGE SECTION OVERLAPS)	OFFSET DISTANCE FROM CENTERLINE OF DITCH	CABLE GUIDERAIL ANCHOR UNITS (EA)	DEDUCTIONS FROM TOTAL GUIDERAIL LENGTH (m) (7.6m FOR EACH ANCHOR)	REMOVE EXISTING GUIDERAIL	REMOVE AND RESET EXISTING GUIDERAIL	REMARKS
-FLYEREV--LREV-	18+10.000	13+28.073	LTMED	1,033.452	1,048.652	2.4	4	30.400			
-LREV--L-	15+47.927	26+84.447	MED	1,136.520	1,151.720	2.4	4	30.400			
-IYI-	13+74.000	15+54.000	MED				2			180.000	FOR TEMPORARY CROSSOVER
-IYI-	16+43.156	17+16.844	MED				2		58.488	15.200	REMOVE AND RESET IS FOR PROPOSED ANCHORS ONLY
-IYI-	18+79.777	19+03.772	MED				1		16.395	7.600	REMOVE AND RESET IS FOR PROPOSED ANCHOR ONLY
-IYI-	19+52.947	19+72.013	MED				1		11.466	7.600	REMOVE AND RESET IS FOR PROPOSED ANCHOR ONLY
-IYI-	23+34.000	25+86.362	MED				2			252.362	FOR TEMPORARY CROSSOVER
-IYI-	26+97.890	28+82.815	MED				2		169.725	15.200	REMOVE AND RESET IS FOR PROPOSED ANCHORS ONLY
-IYI-	30+26.000	32+06.000	MED				2			180.000	FOR TEMPORARY CROSSOVER
			SUBTOTAL R-2552AA:		2,200.372		20	60.800	256.074	657.962	
			LESS ANCHOR DEDUCTIONS R-2552AA:		- 60.800						
			TOTAL R-2552AA:		2,139.572		20		256.074	657.962	
			SAY R-2552AA:		2,150				260	660	
			TOTAL R-2552AB:		2,437.99		10		0	0	
			SAY R-2552AB:		2,450						
			GRAND TOTAL:		4,577.562		30		256.074	657.962	
			GRAND SAY:		4,600				260	660	