



SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
S-215	CL	18+75	0.00-4.25	A-6(2)	35	11	34.7	24.3	20.9	20.1	100	78	45	-	-
SS-303	CL	19+40	0.96-1.41	A-7-5(10)	52	20	27.1	21.8	20.8	30.3	99	82	56	-	-
SS-304	CL	19+40	2.48-2.93	A-5(0)	45	NP	36.4	26.3	23.2	14.1	100	76	46	-	-
SS-305	CL	19+40	4.00-4.45	A-2-4(0)	33	NP	41.6	31.3	19.0	8.1	100	72	34	-	-
S-306	CL	20+00	0.50-1.00	A-7-6(14)	54	27	25.5	20.6	15.6	38.4	100	85	58	-	-
S-307	CL	20+60	0.50-1.00	A-2-4(0)	21	NP	50.7	25.3	11.9	12.1	92	60	26	-	-
S-308	CL	21+20	0.80-1.20	A-7-6(10)	48	26	33.5	18.8	15.4	32.3	99	75	53	-	-
S-309	CL	21+20	1.70-2.10	A-7-6(7)	44	23	31.7	22.0	18.0	28.3	96	74	48	-	-
S-310	CL	21+20	2.80-3.10	A-6(4)	36	19	36.0	23.4	18.4	22.2	96	71	44	-	-
SS-311	5.0 LT	21+90	0.15-0.60	A-2-4(0)	26	NP	45.3	42.0	6.7	6.1	97	74	16	-	-
SS-312	5.0 LT	21+90	1.20-1.65	A-2-4(0)	28	8	48.5	22.6	12.7	16.2	94	63	33	-	-
SS-313	5.0 LT	21+90	4.32-4.69	A-2-4(0)	37	NP	46.1	33.7	14.1	6.1	88	58	22	-	-
S-314	CL	22+40	0.50-0.97	A-7-6(7)	47	22	35.3	21.4	15.1	28.2	98	74	47	-	-
S-315	CL	22+40	2.30-3.00	A-6(3)	38	16	39.5	21.2	19.2	20.2	96	69	42	-	-
SS-316	CL	22+88	1.08-1.53	A-7-5(11)	56	21	25.0	22.8	22.0	30.2	97	82	58	-	-
SS-317	CL	22+88	2.60-3.05	A-7-5(21)	69	37	22.6	18.1	16.9	42.3	98	83	61	-	-
SS-318	CL	22+88	4.32-4.57	A-7-6(12)	52	31	29.4	23.2	21.2	26.2	98	80	51	-	-