

PROJECT R-2552AA

COUNTY WAKE-JOHNSTON

COMPUTED BY: BCF 01/05
 CHECKED BY: SCL 01/05

SHEET 3 OF 6

STATION	STATION	TOTAL EXCAV. (UNCL.)	ROCK EXCAV.	UNDERCUT EXCAV.	UNSUIT. EXCAV.	SUITABLE EARTH EXCAV.	TOTAL EMB.	ROCK EMB.	EARTH EMB.	UNDERCUT EMB.	EMB. + 20 %	BORROW	ROCK WASTE	SUITABLE WASTE	UNSUIT. WASTE	TOTAL WASTE
-YREV-																
10+03.492	17+75.354	12,197	0	0	0	12,197	5,381	0	5,381	0	6,457	0	0	5,740	0	5,740
SUBTOTAL:		12,402	0	0	0	12,402	5,381	0	5,381	0	6,457	0	0	5,945	0	5,945
-IIV1- RT.																
20+00.000	23+60.000	4,510	0	0	0	4,510	416	0	416	0	499	0	0	4,011	0	4,011
-IIV1- RT. INCLUDES -LPB- STA. 23+05.124 TO STA. 23+89.129																
23+60.000	30+00.000	7,888	0	0	0	7,888	1,995	0	1,995	0	2,394	0	0	5,494	0	5,494
-FLYLEREV-																
28+20.000	31+76.908	49,335	0	569	5,911	43,424	3,632	0	3,063	569	4,358	0	0	39,066	6,480	45,546
-FLYLEREV- INCLUDES -LPB- STA. 18+91.307 TO STA. 21+74.736																
24+85.308 END BRIDGE	28+20.000	2,618	0	546	1,234	1,384	51,638	0	51,092	546	61,966	60,582	0	0	1,780	1,780
-LPB-																
21+74.736	23+05.124	0	0	0	0	0	11,109	0	11,109	0	13,331	13,331	0	0	0	0
SUBTOTAL:		64,351	0	1,115	7,145	57,206	68,790	0	67,675	1,115	82,548	73,913	0	48,571	8,260	56,831
-IIV1- RT.																
30+00.000	36+40.000	5,788	0	0	0	5,788	498	0	498	0	598	0	0	5,190	0	5,190
SUBTOTAL:		5,788	0	0	0	5,788	498	0	498	0	598	0	0	5,190	0	5,190
-FLYLEREV- INCLUDES -LPB- STA. 14+19.001 TO 15+95.084																
20+20.000	22+03.308 BEGIN BRIDGE	0	0	0	0	0	51,930	0	51,930	0	62,316	62,316	0	0	0	0
-LPB- (ON -FLYLEREV- X-SECTIONS)																
15+95.084	16+58.307 BEGIN BRIDGE	0	0	0	0	0	10,326	0	10,326	0	12,391	12,391	0	0	0	0
-FLYLWREV-																
19+96.902	23+00.080	4,515	0	1,160	2,395	2,120	4,277	0	3,117	1,160	5,132	3,012	0	0	3,555	3,555
SUBTOTAL:		4,515	0	1,160	2,395	2,120	66,533	0	65,373	1,160	79,839	77,719	0	0	3,555	3,555