PROJECT R-2552AA COUNTY WAKE-JOHNSTON COMPUTED BY: BCF 01/05 CHECKED BY: SCL 01/05 SHEET 4 OF 6

STATION	STATION	TOTAL EXCAV. (UNCL.)	ROCK EXCAV.	UNDERCUT EXCAV.	UNSUIT. EXCAV.	SUITABLE EARTH EXCAV.	TOTAL EMB.	ROCK EMB.	EARTH EMB.	UNDERCUT EMB.	EMB. + 20 %	BORROW	ROCK WASTE	SUITABLE WASTE	UNSUIT. WASTE	TOTAL WASTE
-FLYLEREV- INCLUDES -FLYLWREV- STA. 17+61.543 TO 19+96.902 -LPB- STA 11+83.218 TO 14+19.001																
17+80.000	20+20.000	8	0	0	0	8	54,909	0	54,909	0	65,891	65,883	0	0	0	0
-FLYLEREV- INCLUDES -FLYLWREV- STA. 12+93.096 TO 17+61.543 -RPD- STA 10+14.582 TO 12+40.456 -LPB- STA 10+05.806 TO 11+83.218																
13+00.000	17+80.000	135,972	0	1,398	63,912	72,060	11,489	0	10,091	1,398	13,787	0	0	58,273	65,310	123,583
-RPD-																
12+40.456	15+47.035	10,213	0	0	0	10,213	11,274	0	11,274	0	13,529	3,316	0	0	0	0
SUBTOTAL:		146,193	0	1,398	63,912	82,281	77,672	0	76,274	1,398	93,207	69,199	0	58,273	65,310	123,583
-FLYLEREV- INCLUDES -FLYLWREV- STA. 10+00.000 TO 12+93.096																
10+00.000	13+00.000	121,753	802	0	28,017	92,934	0	0	0	0	0	0	802	92,934	28,017	121,753
-LREV-																
11+04.621	13+58.173 RT. 13+34.173 LT. BEGIN BRIDGES	16,178	0	380	0	16,178	25,243	0	24,863	380	30,291	14,113	0	0	380	380
-SRD-I-																
10+00.000	12+67.294	424	0	617	159	265	1,284	0	667	617	1,541	1,276	0	0	776	776
SUBTOTAL:		138,355	802	997	28,176	109,377	26,527	0	25,530	997	31,832	15,389	802	92,934	29,173	122,909
-LREV-																
15+41.827 RT. 15+17.827 LT. END BRIDGES	18+99.765	92,717	0	0	0	92,717	14,028	0	14,028	0	16,834	0	0	75,883	0	75,883
-L-																
18+99.765	28+00.000	94,989	0	885	0	94,989	58,611	0	57,726	885	70,333	0	0	24,656	885	25,541
SUBTOTAL:		187,706	0	885	0	187,706	72,639	0	71,754	885	87,167	0	0	100,539	885	101,424