R:\proj\interim\xsc\earth\y1ltew1.log

PROJ. REFERENCE NO.	SHEET NO.
R-2552AA	X-D

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station Y2B	Uncl. Exc. (cu. meters)	Embt (cu. meters)
13+80.000	2308	0
14+00.000	2062	0
14+20.000	1307	0
14+40.000	500	124
14+60.000	109	471
14+80.000	53	388
15+00.000	55	78
15+20.000	38	291
15+40.000	0	642
15+60.000	0	1063
15+80.000	0	1803
16+00.000	0	2626
16+20.000	0	2177
16+40.000	0	878
16+60.000	8	232
16+80.000	97	34
17+00.000	226	0
17+20.000	285	0
17+40.000	275	0
17+60.000	209	0
17+80.000	179	0
18+00.000	160	27
18+20.000	120	73
18+40.000	128	55
18+60.000	265	9
18+80.000	519	0
19+00.000	601	0
19+20.000	487	0
19+28.404	89	0

Station Y4	Uncl. Exc. (cu. meters)	Embt (cu. meters)
12+50.000	0	0
12+80.000	115	0
13+00.000	139	0
13+20.000	93	5
13+40.000	50	45
13+60.000	32	110
13+80.000	12	170
14+00.000	0	213
14+07.721	0	86
14+87.121	0	0
15+00.000	147	11
15+20.000	268	8
15+40.000	303	0
15+60.000	254	0
15+80.000	184	0
15+95.000	59	0

Station Y4Det	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+00.000	0	0
10+20.000	6	1
10+40.000	18	4
10+60.000	17	43
10+80.000	13	135
11+00.000	49	155
11+20.000	164	66
11+40.000	423	6
11+55.235	458	0

Station Srd-1	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+00.000	0	0
10+20.000	51	0
10+40.000	61	11
10+60.000	10	77
10+80.000	0	158
11+00.000	0	165
11+20.000	0	139
11+40.000	33	73
11+60.000	55	8
11+80.000	32	11
12+00.000	19	18
12+20.000	39	7
12+40.000	57	0
12+60.000	50	0
12+67.294	17	0

Station Dr2	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+03.477	0	0
10+20.000	1017	0
10+40.000	898	0
10+60.000	332	0
10+64.260	21	0