

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201258

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000010000-N	800	Lump Sum		MOBILIZATION	202200000-E	815	67.2	CY	SUBDRAIN EXCAVATION	364900000-E	876	26	TON	PLAIN RIP RAP, CLASS B
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+99.00 -L-)	203300000-E	815	50.4	CY	SUBDRAIN FINE AGGREGATE	365600000-E	876	1,080	SY	FILTER FABRIC FOR DRAINAGE
004300000-N	226	Lump Sum		GRADING	204400000-E	815	300	LF	6" PERFORATED SUBDRAIN PIPE	365900000-N	SP	2	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING	205500000-E	815	9	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	441200000-E	SP	154	SF	WORK ZONE SIGNS (STATIONARY)
005700000-E	226	500	CY	UNDERCUT EXCAVATION	206600000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	441210000-E	SP	96	SF	WORK ZONE SIGNS (PORTABLE)
008000000-E	SP	600	TON	CLASS IV SUBGRADE STABILIZATION	207700000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)	441220000-E	SP	32	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
019500000-E	265	500	CY	SELECT GRANULAR MATERIAL	219900000-E	SP	1,235	SF	SANDBAG HEADWALL	443000000-N	1130	30	EA	DRUMS
019600000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION	228600000-N	840	4	EA	MASONRY DRAINAGE STRUCTURES	443500000-N	1135	15	EA	CONES
024100000-E	SP	480	SY	GENERIC GRADING ITEM ROCK-PLATED EMBANKMENT	236600000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.24	444610000-E	SP	48	LF	BARRICADES (TYPE III)
031800000-E	300	24	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	236700000-N	840	3	EA	FRAME WITH TWO GRATES, STD 840.29	445000000-N	1150	2,400	HR	FLAGGER
036600000-E	310	92	LF	15" RC PIPE CULVERTS, CLASS III	251600000-E	SP	135	CY	SELECT GRANULAR MATERIAL FOR TEMPORARY FABRIC WALL	446500000-N	1160	1	EA	TEMPORARY CRASH CUSHIONS
057600000-E	310	105	LF	*** CS PIPE CULVERTS, ***** THICK (96", 0.109")	251700000-E	SP	950	SY	FABRIC FOR TEMPORARY FABRIC WALL	447500000-N	1165	2	EA	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)
058200000-E	310	24	LF	15" CS PIPE CULVERTS, 0.064" THICK	255600000-E	846	60	LF	SHOULDER BERM GUTTER	448500000-E	1170	300	LF	PORTABLE CONCRETE BARRIER
099500000-E	340	105	LF	PIPE REMOVAL	257700000-E	846	105	LF	CONCRETE EXPRESSWAY GUTTER	465000000-N	1251	38	EA	TEMPORARY RAISED PAVEMENT MARKERS
099600000-N	350	1	EA	PIPE CLEAN-OUT	261900000-E	850	20	SY	4" CONCRETE PAVED DITCH	481000000-E	1205	8,700	LF	PAINT PAVEMENT MARKING LINES (4")
112100000-E	520	115	TON	AGGREGATE BASE COURSE	303000000-E	862	75	LF	STEEL BM GUARDRAIL	483500000-E	1205	40	LF	PAINT PAVEMENT MARKING LINES (24")
122000000-E	545	50	TON	INCIDENTAL STONE BASE	304500000-E	862	25	LF	STEEL BM GUARDRAIL, SHOP CURVED	490000000-N	1252	58	EA	PERMANENT RAISED PAVEMENT MARKERS
133000000-E	607	100	SY	INCIDENTAL MILLING	315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	600000000-E	1605	580	LF	TEMPORARY SILT FENCE
148900000-E	610	205	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	318000000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (TYPE III, SHOP CURVED)	600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
152500000-E	SP	140	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	319500000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1	600900000-E	1610	110	TON	STONE FOR EROSION CONTROL, CLASS B
156000000-E	620	18	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	321500000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE III	601200000-E	1610	235	TON	SEDIMENT CONTROL STONE
169300000-E	654	30	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	327000000-N	SP	2	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	601500000-E	1615	0.5	ACR	TEMPORARY MULCHING
200000000-N	806	12	EA	RIGHT OF WAY MARKERS	338000000-E	862	250	LF	TEMPORARY STEEL BM GUARDRAIL	601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
					338910000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
										602400000-E	1622	40	LF	TEMPORARY SLOPE DRAINS
										ItemNumber	Sec #	Quantity	Unit	Description
										602700000-N	1622	1	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
										602900000-E	SP	500	LF	SAFETY FENCE
										603000000-E	1630	170	CY	SILT EXCAVATION
										603600000-E	1631	435	SY	MATTING FOR EROSION CONTROL
										604200000-E	1632	80	LF	1/4" HARDWARE CLOTH
										607000000-N	SP	8	EA	SPECIAL STILLING BASINS
										608400000-E	1660	0.5	ACR	SEEDING & MULCHING
										608700000-E	1660	0.5	ACR	MOWING
										609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
										609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
										609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
										610800000-E	1665	0.5	TON	FERTILIZER TOPDRESSING
										611400000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
										611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
										612300000-E	1670	0.28	ACR	REFORESTATION