

DIVISION OF HIGHWAYS  
 STATE OF NORTH CAROLINA

**SUMMARY OF EARTHWORK**  
 IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
SUMMARY #1					
-L- Sta. 8+00.00 (Beg. Const.) TO 16+30.50 (Beg. Bridge)	1,184		5,382	4,198	0
-L- Sta. 17+80.50 (End Bridge) TO 25+25.36 (End Const.)	653		7,390	6,737	0
SUMMARY NO. 1 SUBTOTAL	1,837		12,772	10,935	0
EST. SHOULDER CONSTRUCTION			704	704	
PROJECT SUBTOTAL	1,837		13,476	11,639	0
EST. 5% FOR REPLACING TOPSOIL ON BORROW PIT				582	
EST. LOSS DUE TO CLEARING AND GRUBBING	-25			25	
PROJECT TOTAL	1,812		13,476	12,246	
GRAND TOTAL	1,812			12,246	
SAY	1,850			12,300	

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING"

CONTINGENCY UNDERCUT = 500 CY  
 CONTINGENCY SELECT MATERIAL CLASS II OR III = 1,000 CY  
 CONTINGENCY CLASS IV SUBGRADE STABILIZATION = 1,000 TONS  
 ESTIMATED DDE = 10 CY

**RIGHT OF WAY AREA DATA**

PARCEL NO.	PROPERTY OWNERS NAMES	TOTAL ACREAGE	AREA TAKEN	AREA REMAINING RT.	AREA REMAINING LT.	CONST. EASE.	PERM. DRAIN. EASE.	TEMP. DRAIN. EASE.
1	HUTCHINSONS L.L.C.	305.42 AC	2.11 AC	208.26 AC	95.05 AC	0.46 AC		
2	JAMES GUY HUTCHINSON	103.17 AC	1.66 AC		101.51 AC	0.28 AC		

**PAVEMENT REMOVAL**  
 IN SQUARE YARDS

LINE	LTRT	STATION TO STATION	SQ. YDS
-L-	-CL-	11+60 - 12+99	139.7
-L-	-CL-	13+36 - 16+45	409.3
-L-	-CL-	17+72 - 21+40	251.3
		PROJECT TOTAL	800.3
		SAY	820 SY

6/4/99

21-DEC-2004 14:20  
 R:\Roadway\Prep\103714\RDY\_SUM.dgn  
 avoaland AT 10/21/07