

DIVISION OF HIGHWAYS  
 STATE OF NORTH CAROLINA

**SUMMARY OF QUANTITIES**

STATE OF NORTH CAROLINA  
 DIVISION OF HIGHWAYS  
 ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200891

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	1693000000-E	654	10	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	4435000000-N	1135	60	EA	CONES
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING	2000000000-N	806	10	EA	RIGHT OF WAY MARKERS	4446100000-E	SP	40	LF	BARRICADES (TYPE III)
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+05.5-L-)	2022000000-E	815	230	CY	SUBDRAIN EXCAVATION	4450000000-N	1150	320	HR	FLAGGER
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING	2033000000-E	815	170	CY	SUBDRAIN FINE AGGREGATE	4465000000-N	1160	2	EA	TEMPORARY CRASH CUSHIONS
0057000000-E	226	500	CY	UNDERCUT EXCAVATION	2044000000-E	815	1,000	LF	6" PERFORATED SUBDRAIN PIPE	4485000000-E	1170	245	LF	PORTABLE CONCRETE BARRIER
0063000000-N	SP	Lump Sum		GRADING	2055000000-E	815	30	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	4495000000-E	1170	222	LF	PORTABLE CONCRETE BARRIER (DRAINAGE)
0080000000-E	SP	1,000	TON	CLASS IV SUBGRADE STABILIZATION	2066000000-N	815	2	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	4650000000-N	1251	22	EA	TEMPORARY RAISED PAVEMENT MARKERS
0106000000-E	230	12,300	CY	BORROW EXCAVATION	2077000000-E	815	12	LF	6" OUTLET PIPE (SUBDRAINS)	4730000000-E	1205	6,900	LF	EPOXY PAVEMENT MARKING LINES (4")
0134000000-E	240	10	CY	DRAINAGE DITCH EXCAVATION	2286000000-N	840	4	EA	MASONRY DRAINAGE STRUCTURES	4810000000-E	1205	13,800	LF	PAINT PAVEMENT MARKING LINES (4")
0195000000-E	265	1,000	CY	SELECT GRANULAR MATERIAL	2308000000-E	840	1.64	LF	MASONRY DRAINAGE STRUCTURES	4850000000-E	1205	400	LF	REMOVAL OF PAVEMENT MARKING LINES (4")
0196000000-E	270	1,000	SY	FABRIC FOR SOIL STABILIZATION	2366000000-N	840	3	EA	FRAME WITH TWO GRATES, STD 840.24	4900000000-N	1252	2	EA	PERMANENT RAISED PAVEMENT MARKERS
0199000000-E	SP	230	SF	TEMPORARY SHORING	2367000000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.29	4905000000-N	1253	19	EA	SNOWPLOWABLE PAVEMENT MARKERS
0318000000-E	300	29	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	2556000000-E	846	10	LF	SHOULDER BERM GUTTER	5300000000-E	1505	12	TON	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)
0366000000-E	310	140	LF	15" RC PIPE CULVERTS, CLASS III	3030000000-E	862	362.5	LF	STEEL BM GUARDRAIL	5306000000-E	SP	12	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)
0378000000-E	310	120	LF	24" RC PIPE CULVERTS, CLASS III	3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	5444000000-E	1510	238	LF	6" PVC WATER PIPE, SDR ***** (SDR 21, 200# WP)
0714000000-E	310	8	LF	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	5480000000-E	1510	300	LB	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP
0807000000-E	310	2	EA	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	5540000000-E	1510	2	EA	6" GATE VALVE & VALVE BOX, 200# WP
0995000000-E	340	110	LF	PIPE REMOVAL	3387000000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (W-BEAM)	5888000000-E	SP	416	LF	GENERIC UTILITY ITEM 8" HDPE WATER PIPE, SDR 9, 200 # WP BY DIRECTIONAL BORE
1220000000-E	545	75	TON	INCIDENTAL STONE BASE	3649000000-E	876	25	TON	PLAIN RIP RAP, CLASS B	6000000000-E	1605	2,190	LF	TEMPORARY SILT FENCE
1489000000-E	610	1,550	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	3656000000-E	876	200	SY	FILTER FABRIC FOR DRAINAGE	6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
1498000000-E	610	1,220	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3659000000-N	SP	2	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	6009000000-E	1610	380	TON	STONE FOR EROSION CONTROL, CLASS B
1519000000-E	610	880	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4412000000-E	SP	84	SF	WORK ZONE SIGNS (STATIONARY)	6012000000-E	1610	160	TON	SEDIMENT CONTROL STONE
1560000000-E	620	182	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4412100000-E	SP	96	SF	WORK ZONE SIGNS (PORTABLE)	6015000000-E	1615	5	ACR	TEMPORARY MULCHING
					4412200000-E	SP	20	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	6018000000-E	1620	200	LB	SEED FOR TEMPORARY SEEDING
					4430000000-N	1130	60	EA	DRUMS	6021000000-E	1620	0.75	TON	FERTILIZER FOR TEMPORARY SEEDING
										6024000000-E	1622	240	LF	TEMPORARY SLOPE DRAINS
										6027000000-N	1622	5	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
										6029000000-E	SP	800	LF	SAFETY FENCE
										6030000000-E	1630	900	CY	SILT EXCAVATION
										6036000000-E	1631	700	SY	MATTING FOR EROSION CONTROL
										6042000000-E	1632	20	LF	1/4" HARDWARE CLOTH
										6084000000-E	1660	5.5	ACR	SEEDING & MULCHING
										6087000000-E	1660	3	ACR	MOWING
										6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
										6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
										6096000000-E	1662	125	LB	SEED FOR SUPPLEMENTAL SEEDING
										6108000000-E	1665	4.25	TON	FERTILIZER TOPDRESSING
										6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
										6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
										6123000000-E	1670	0.25	ACR	REFORESTATION

10/11/2004  
 H:\Roadway\Proj\B3714-RDY\SUM.dgn