

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201243

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
3000000000-N	SP	1	EA	IMPACT ATTENUATOR UNIT, TYPE 350
3030000000-E	862	11,000	LF	STEEL BM GUARDRAIL
3150000000-N	862	10	EA	ADDITIONAL GUARDRAIL POSTS
3180000000-N	862	8	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (TYPE III MOD)
3210000000-N	862	87	EA	GUARDRAIL ANCHOR UNITS, TYPE CAT-1
3270000000-N	SP	132	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3317000000-N	862	51	EA	GUARDRAIL ANCHOR UNITS, TYPE B-77
3360000000-E	863	14,000	LF	REMOVE EXISTING GUARDRAIL
4412100000-E	SP	1,348	SF	WORK ZONE SIGNS (PORTABLE)
4415000000-N	1115	4	EA	FLASHING ARROW PANELS, TYPE C
4420000000-N	1120	4	EA	CHANGEABLE MESSAGE SIGNS
4430000000-N	1130	500	EA	DRUMS
4435000000-N	1135	60	EA	CONES
4450000000-N	1150	480	HR	FLAGGER
4480000000-N	1165	6	EA	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)
6087000000-E	1660	18.5	ACR	MOWING
6109000000-E	SP	1.5	ACR	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BUEGRASS)
6114000000-N	SP	18.5	HR	SPECIALIZED HAND MOWING

5/14/99

II-MAR-2005_08:41
P:\Roadway\pcoj\4414_r.dj--tjg.dgn
BPRobinson