

C201434

PROJECT SPECIAL PROVISIONS  
EROSION CONTROL

GRANVILLE CO.

SEEDING AND MULCHING:

THE KINDS OF SEED AND FERTILIZER, AND THE RATES OF APPLICATION OF SEED, FERTILIZER, AND LIMESTONE, SHALL BE AS STATED BELOW. DURING PERIODS OF OVERLAPPING DATES, THE KIND OF SEED TO BE USED SHALL BE DETERMINED BY THE ENGINEER. ALL RATES ARE IN POUND PER ACRE.

PO2A

JANUARY 1 – DECEMBER 31

- 50# TALL FESCUE
- 5# CENTIPEDE
- 50# PENSACOLA BAHIAGRASS
- 500# FERTILIZER
- 4000# LIMESTONE

SLOPES STEEPER THAN 2:1:

JANUARY 1 – DECEMBER 31

- 75# TALL FESCUE
- 50# PENSACOLA BAHIAGRASS
- 500# FERTILIZER
- 4000# LIMESTONE

PO3A

APPROVED TALL FESCUE CULTIVARS:

ADVENTURE	ADVENTURE II	AMIGO	ANTHEM
APACHE	APACHE II	ARID	BROOKSTONE
BONANZA	BONANZA	CHESAPEAKE	FINELAWN
CORONADO	CROSSFIRE II	DUBUTANTE	DUSTER
FALCON	FALCON II	FINELAWN PETITE	FINELAWN
FINELAWN I	GENESIS	GRANDE	GUARDIAN
HOUNDDOG	JAGUAR	JAGUAR III	KENTUCKY 31
KITTY HAWK	MONARCH	MONTAUK	MUSTANG
OLYMPIC	PACER	PIXIE	PYRAMID
REBEL	REBEL JR.	REBEL II	RENEGADE
SAFARI	SHENANDOAH	TITAN	TOMAHAWK
TRAILBLAZER	TRIBUTE	WRANGLER	

PO4A

FERTILIZER SHALL BE 10-20-20 ANALYSIS. UPON WRITTEN APPROVAL OF THE ENGINEER, A DIFFERENT ANALYSIS OF FERTILIZER MAY BE USED PROVIDED THE 1-2-2 RATIO IS MAINTAINED AND THE RATE OF APPLICATION ADJUSTED TO PROVIDE THE SAME AMOUNT OF PLANT FOOD AS A 10-20-20 ANALYSIS.

P11A

THE QUANTITY OF SEEDING AND MULCHING TO BE PAID FOR WILL BE THE ACTUAL NUMBER OF ACRES OF SEEDING AND MULCHING, MEASURED ALONG THE SURFACE OF THE GROUND, WHICH HAS BEEN COMPLETED AND ACCEPTED. THE QUANTITY OF SEEDING AND MULCHING, MEASURED AS NOTED, WILL BE PAID FOR AT THE CONTRACT PRICE FOR "SEEDING AND MULCHING."