

STATE OF NORTH CAROLINA
SUMMARY OF QUANTITIES

PROJECT REFERENCE No.	SHEET No.
C201464	3

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201464

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
0241000000-E	SP	2,900	SY	GENERIC GRADING ITEM GALVANIZED CHAINLINK MESH
0241000000-E	SP	7,250	SY	GENERIC GRADING ITEM RING NET
0255000000-E	SP	2,175	TON	GENERIC GRADING ITEM RIP RAP MATERIALS, CLASS A
0257000000-E	SP	360	LF	GENERIC GRADING ITEM GROUTED ROCK DOWEL
0314000000-E	SP	16,350	TON	SELECT MATERIAL, CLASS ***** (VII)
0318000000-E	300	34	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0720000000-E	310	320	LF	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0808000000-E	310	2	EA	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
0995000000-E	340	30	LF	PIPE REMOVAL
1297000000-E	607	280	SY	MILLING ASPHALT PAVEMENT, **** DEPTH (2")
1330000000-E	607	30	SY	INCIDENTAL MILLING
1491000000-E	610	430	TON	ASPHALT CONC BASE COURSE, TYPE B25.0C
1508000000-E	610	50	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0D
1539000000-E	610	100	TON	ASPHALT CONC SURFACE COURSE, TYPE S12.5C
1560000000-E	620	20	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1565000000-E	620	10	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
1840000000-E	665	500	LF	MILLED RUMBLE STRIPS
1891000000-E	SP	110	SY	GENERIC PAVING ITEM UNREINFORCED CONCRETE

ItemNumber	Sec #	Quantity	Unit	Description
2286000000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES
2308000000-E	840	1	LF	MASONRY DRAINAGE STRUCTURES
2396000000-N	840	1	EA	FRAME WITH COVER, STD 840.54
2407000000-N	840	2	EA	STEEL FRAME WITH TWO GRATES, STD 840.37
2703000000-E	854	500	LF	CONCRETE BARRIER, TYPE ***** (STD 854.02 T)
2938000000-N	SP	1	EA	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE COVER
3628000000-E	876	30	TON	PLAIN RIP RAP, CLASS I
3656000000-E	876	150	SY	FILTER FABRIC FOR DRAINAGE
3980000000-E	SP	50	CY	GENERIC WALL ITEM GROUT FOR TIEBACK ANCHORS AT WALL AT SLIDE #4
3984000000-E	SP	4,850	SF	GENERIC WALL ITEM PERMANENT ANCHOR TIEBACK WALL AT SLIDE #4
4412000000-E	SP	96	SF	WORK ZONE SIGNS (STATIONARY)
4412100000-E	SP	104	SF	WORK ZONE SIGNS (PORTABLE)
4415000000-N	1115	1	EA	FLASHING ARROW PANELS, TYPE C
4420000000-N	1120	1	EA	CHANGEABLE MESSAGE SIGNS
4430000000-N	1130	45	EA	DRUMS
4465000000-N	1160	1	EA	TEMPORARY CRASH CUSHIONS
4480000000-N	1165	1	EA	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)
4485000000-E	1170	700	LF	PORTABLE CONCRETE BARRIER
4500000000-E	1170	1,430	LF	RESET PORTABLE CONCRETE BARRIER
6000000000-E	1605	1,300	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	40	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	125	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	2.5	ACR	TEMPORARY MULCHING

ItemNumber	Sec #	Quantity	Unit	Description
6018000000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING
6030000000-E	1630	60	CY	SILT EXCAVATION
6036000000-E	1631	5,250	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	380	LF	1/4" HARDWARE CLOTH
6084000000-E	1660	2	ACR	SEEDING & MULCHING
6087000000-E	1660	0.5	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1.5	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	1	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
6123000000-E	1670	1	ACR	REFORESTATION