COMPUTED BY:	PRIDGEN	DATE:	12–17–04
CHECKED BY:		DATE:	

PROJECT REFERENCE NO.	SHEET NO.
B-3887	3-A
PAW SHEET NO	

SUMMARY OF EARTHWORK

IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT+%	BORROW	WASTE
SUMMARY NO. 1					
-L- LINE					
STA. 11 + 40.00 TO STA. 15 + 07.12 (BRIDGE)	281		839	558	
SUMMARY NO. 2					
-L- LINE		·			
STA. 16 + 22.13 (BRIDGE) TO STA. 21 + 00.00	461		2023	1564	
SUB TOTAL	742		2862	2122	
EST. 5% FOR REPLACING TOPSOIL IN BORROW			2002	106	
GRAND TOTAL	742			2228	
SAY	750			2300	

UNDERCUT – 200 C.Y.

APPROXIMATE QUANTITIES ONLY. UCLASSIFIED EXCAVATION, BORROW EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING".

ASPHALT PAVEMENT REMOVAL SUMMARY

LINE	STATION TO STATION	LOCATION	SQ. YD.
-L	11 + 40.00 - 15 + 28.00	CL	862
_L _	16+14.00 - 21+00.00	CL	1080
		TOTAL	1942
		SAY	2000

APPROXIMATE QUANTITIES ONLY. UCLASSIFIED EXCAVATION, BORROW EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING".