

**PROJECT: B-3887**  
**COUNTY: PENDER**

**PROJECT SPECIAL PROVISIONS**  
**UTILITY**

**GENERAL:**

**THE FOLLOWING UTILITY COMPANIES HAVE FACILITIES THAT WILL BE IN CONFLICT WITH THE CONSTRUCTION OF THIS PROJECT:**

- A. FOUR COUNTY EMC (Distribution)**
- B. BELLSOUTH**

**THE CONFLICTING FACILITIES OF THESE CONCERNS WILL BE ADJUSTED PRIOR TO THE DATE OF AVAILABILITY UNLESS OTHERWISE NOTED AND ARE THEREFORE LISTED IN THESE SPECIAL PROVISIONS FOR THE BENEFIT OF THE CONTRACTOR. ALL UTILITY WORK LISTED HEREIN WILL BE DONE BY THE UTILITY OWNERS. ALL UTILITIES ARE SHOWN ON THE PLANS FROM THE BEST AVAILABLE INFORMATION.**

**THE CONTRACTOR'S ATTENTION IS DIRECTED TO ARTICLE 105-8 OF THE STANDARD SPECIFICATIONS.**

- A. FOUR COUNTY EMC (Distribution)**  
**(SEE UTILITIES BY OTHERS PLANS FOR DETAILS)**

Note: Four County EMC will remove the proposed span guy that crosses Old Maple Hill Rd at approximate station 14+50 for up to a 30 day period, if needed, during the construction process. Four County EMC will need two (2) days notice and one day construction time to complete this work.

- B. BELLSOUTH**  
**(SEE UTILITIES BY OTHERS PLANS FOR DETAILS)**

1. Station 10+00 to Station 21+00 Line -L-  
A new underground telephone line will be installed right of line -L- between Station 10+00 and Station 21+00. BellSouth will require two (2) weeks notice and three (3) weeks to complete the work after clearing and grubbing.

Note: Permanent Utility Easement to be cleared and grubbed by NCDOT contractor.