

**B-3839**

**66**  
**Project Special Provisions**  
**Erosion Control**

**Forsyth County****Seeding and Mulching:**

(West)

The kinds of seed and fertilizer, and the rates of application of seed, fertilizer, and limestone, shall be as stated below. During periods of overlapping dates, the kind of seed to be used shall be determined by the Engineer. All rates are in pounds per acre (kilograms per hectare).

## Shoulder and Median Areas:

August 1 - June 1

May 1 - September 1

20# (23kg) Kentucky Bluegrass	20# (23kg) Kentucky Bluegrass
75# (85kg) Hard Fescue	75# (85kg) Hard Fescue
25# (28kg) Rye Grain	10# (12kg) German or Browntop Millet
500# (560kg) Fertilizer	500# (560kg) Fertilizer
4000# (4500kg) Limestone	4000# (4500kg) Limestone

## Areas Beyond the Mowing Pattern, Waste and Borrow Areas:

August 1 - June 1

May 1 - September 1

100# (110kg) Tall Fescue	100# (110kg) Tall Fescue
15# (17kg) Kentucky Bluegrass	15# (17kg) Kentucky Bluegrass
30# (34kg) Hard Fescue	30# (34kg) Hard Fescue
25# (28kg) Rye Grain	10# (12kg) German or Browntop Millet
500# (560kg) Fertilizer	500# (560kg) Fertilizer
4000# (4500kg) Limestone	4000# (4500kg) Limestone

## Approved Tall Fescue Cultivars:

Adventure	Adventure II	Amigo	Anthem
Apache	Apache II	Arid	Austin
Brookstone	Bonanza	Bonanza II	Chapel Hill
Chesapeake	Chieftain	Coronado	Crossfire II
Debutante	Duster	Falcon	Falcon II
Finelawn Petite	Finelawn	Finelawn I	Genesis
Grande	Guardian	Houndog	Jaguar
Jaguar III	Kentucky 31	Kitty Hawk	Monarch
Montauk	Mustang	Olympic	Pacer
Phoenix	Pixie	Pyramid	Rebel
Rebel Jr.	Rebel II	Renegade	Safari
Shenandoah	Tempo	Titan	Tomahawk

Trailblazer	Tribute	Vegas	Wolfpack
Wrangler			

Approved Kentucky Bluegrass Cultivars:

Adelphi	Baron	Bristol	Challenger
Columbia	Fylking	Glade	Kenblue
Merit	Plush	Ram I	Rugby
Sydsport	Touchdown	Vantage	

Approved Hard Fescue Cultivars:

Aurora	Bardur	Crystal	Reliant	Scaldis
Spartan	Valda	Waldina	Warwick	

On cut and fill slopes 2:1 or steeper add 20# (23kg) Sericea Lespedeza January 1 - December 31.

Fertilizer shall be 10-20-20 analysis. Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 1-2-2 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as a 10-20-20 analysis.

**Native Grass Seeding And Mulching**

**Bluegrass**

Native Grass Seeding and Mulching shall be performed on the disturbed areas of wetlands, and adjacent to Stream Relocation and/or Trout Stream construction within a 50 foot (16 meter) zone on both sides of the stream(or depression), measured from top of stream bank, (or center of depression). The stream bank of the Stream Relocation shall be seeded by hand, hydroseeder within permit compliance, and/or other method that does not alter the typical cross section of the stream bank. Native Grass Seeding and Mulching shall also be performed in the Permanent Soil Reinforcement Mat section of Prefomed Scour Holes.

The kinds of seed and fertilizer, and the rates of application of seed, fertilizer, and limestone, shall be as stated below. During periods of overlapping dates, the kind of seed to be used shall be determined by the Engineer. All rates are in pounds per acre (kilograms per hectare).

August 1 - June 1

May 1 - September 1

25# (28kg) Kentucky Bluegrass	25# (28kg) Kentucky Bluegrass
8# (9kg) Big Bluestem	8# (9kg) Big Bluestem
6# (7kg) Indiangrass	6# (7kg) Indiangrass
4#(5kg) Switchgrass	4#(5kg) Switchgrass
35#(39kg) Rye Grain	25#(28kg) German or Browntop Millet
500# (560kg) Fertilizer	500# (560kg) Fertilizer
4000# (4500kg) Limestone	4000# (4500kg) Limestone

**Approved Kentucky Bluegrass Cultivars:**

Adelphi	Baron	Bristol	Challenger
Columbia	Fylking	Glade	Kenblue
Merit	Plush	Ram I	Rugby
Sydsport	Touchdown	Vantage	

Fertilizer shall be 10-20-20 analysis. Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 1-2-2 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as a 10-20-20 analysis.

Native Grass Seeding and Mulching shall be performed in accordance with Section 1660 of the Standard Specifications and vegetative cover sufficient to restrain erosion shall be installed immediately following grade establishment.

**Temporary Seeding:**

Fertilizer shall be the same analysis as specified for "Seeding and Mulching" and applied at the rate of 400 pounds (450kg) and seeded at the rate of 50 pounds per acre (55kg per hectare). German Millet, or Browntop Millet shall be used in summer months and rye grain during the remainder of the year. The Engineer will determine the exact dates for using each kind of seed.

**Fertilizer Topdressing:**

Fertilizer used for topdressing shall be 16-8-8 grade and shall be applied at the rate of 500 pounds per acre (560 kg per hectare). Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 2-1-1 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as 16-8-8 analysis.

**Supplemental Seeding:**

The kinds of seed and proportions shall be the same as specified for "Seeding and Mulching", and the rate of application may vary from 25# to 75# per acre (28kg to 85kg per hectare). The actual rate per acre (hectare) will be determined by the Engineer prior to the time of topdressing and the Contractor will be notified in writing of the rate per acre (hectare), total quantity needed, and areas on which to apply the supplemental seed. Minimum tillage equipment, consisting of a sod seeder shall be used for incorporating seed into the soil as to prevent disturbance of existing vegetation. A clodbuster (ball and chain) may be used where degree of slope prevents the use of a sod seeder.

**Mowing:**

The minimum mowing height on this project shall be six inches (150 mm).

**Lawn Type Appearance**

All areas adjacent to lawns must be hand finished as directed by the Engineer to give a "lawn type appearance". Remove all trash, debris, and stones  $\frac{3}{4}$  inch (19 mm) and larger in diameter or other obstructions that could interfere with providing a smooth "lawn type appearance". These areas shall be reseeded to match their original vegetative conditions, unless directed otherwise by the Field Operations Engineer.

**Specialized Hand Mowing:**

The work covered by this section consists of specialized hand mowing around or under fixed objects, including but not limited to guardrails, signs, barriers and slopes in a method acceptable to the Engineer.

The work of specialized hand mowing shall be completed with mechanically powered trimmers, string trimmers, hand operated rotary mowers, or self-propelled mowers of sufficient size and quality to perform the work timely and efficiently.

The quantity of mowing to be performed will be affected by the actual conditions which occur during the construction of the project. The quantity of mowing may be increased, decreased or eliminated entirely at the direction of the Engineer. Such variations in quantity will not be considered as alterations in the details of construction or a change in the character of the work.

Payment for such work shall be included in the contract bid price for "Lump Sum – Roadway Construction."

**Minimize Removal Of Vegetation**

The Contractor shall minimize removal of vegetation at stream banks and disturbed areas within the project limits as directed by the Engineer.

**Stockpile Areas**

The Contractor shall install and maintain erosion control devices sufficient to contain sediment around any erodible material stockpile areas as directed by the Engineer.

**Waste Areas And Borrow Sources:**

Payment for temporary erosion control measures, except those made necessary by the Contractor's own negligence or for his own convenience, shall be included in the contract bid price for "Lump Sum - Roadway Construction" for the devices or measures utilized in borrow sources and waste areas.

No additional payment will be made for erosion control devices or permanent seeding and mulching in any commercial borrow or waste pit. All erosion and sediment control practices which may be required on a commercial borrow or waste site will be done at the Contractor's expense.

**Temporary Diversion:**

The work by this section for installation, maintenance, and cleanout of temporary diversions shall be in accordance with Section 1630. Payment for installation and cleanout shall be included in the contract bid price for "Lump Sum – Roadway Construction."

**Safety Fence:**

## Description:

The work of "Safety Fence" shall consist of furnishing, installing and maintaining polyethylene or polypropylene fence along the outside riparian buffer, wetland, or water boundary located within the construction corridor to mark the areas that have been approved to infringe within the buffer, wetland or water, and as directed by the Engineer in accordance with the special provisions included herein. The fence shall be installed prior to any land disturbing activities.

## Materials:

## Fence Material:

Polyethylene or polypropylene fence shall be a preconstructed safety fence approved by the Engineer.

## Posts:

Either wood posts or steel posts may be used. Wood posts shall be nominal 2" x 4" (51 mm x 102 mm) or 4" x 4" (102 mm x 102 mm), lengths as required, structural light framing, grade No. 2, Southern Pine. Steel posts shall be at least 5 feet (1.6 m) in length, approximately 1 3/8" (35 mm) wide measured parallel to the fence, and have a minimum weight of 1.25 lb./ft. (1.9 kg/m) of length. The steel post shall be equipped with an anchor plate having a minimum area of 14 square inches (90 square centimeters).

## Clearing and Grading:

No additional clearing and grubbing is anticipated for the installation of this fence; however, if any clearing and grubbing is required, it will be the minimum required for the installation of the safety fence. Such clearing shall include satisfactory removal and disposal of all trees, brush, stumps and other objectionable material.

The fence shall be erected to conform to the general contour of the ground. When determined necessary by the Engineer, minor grading along the fence line shall be done to meet this requirement provided no obstructions to proper drainage are created.

**Installation:**

Posts shall be set and maintained in a vertical position and may be hand set or set with a post driver. If hand set, all backfill material shall be thoroughly tamped. If power driven, wood posts may be sharpened to a dull point. Posts damaged by power driving shall be removed and replaced prior to final acceptance. The tops of all wood posts shall be cut at a 30 degree angle. The wood posts may, at the option of the Contractor, be cut at this angle either before or after the posts are erected.

The fence fabric shall be attached to the wood posts with one 2" (51 mm) galvanized wire staple across each cable or to the steel posts with wire or other acceptable means.

The Contractor shall be required to maintain the safety fence in a satisfactory condition for the duration of the project as determined by the Engineer.

**Basis of Payment:**

Payment for the safety fence shall be included in the contract bid price for "Lump Sum - Roadway Construction." Such payment will be full compensation for the work as described in the above paragraphs, including but not limited to clearing and grading, furnishing and installing fence fabric with necessary posts and post bracing, staples, tie wires, tools, equipment and incidentals necessary to complete the work.

**Gravel Construction Entrance:****Description:**

The work covered by this section consists of furnishing, installing, and maintaining and removing any and all material required for the construction of a Gravel Construction Entrance.

**Materials:**

The filter fabric shall meet the requirements of Section 1056 for Type 2 Fabric.

Stone shall be Class A Stone and shall meet the requirements of Section 1042 for Stone for Erosion Control, Class A.

**Construction:**

The Contractor shall install a Gravel Construction Entrance in accordance with the details in the plans and at locations as directed by the Engineer.

**Method Of Measurement:**

Gravel Construction Entrance will not be measured for payment under this section.

**Basis Of Payment:**

Payment for Gravel Construction Entrance shall be included in the contract bid price for "Lump Sum - Roadway Construction."

Such price and payment shall be considered full compensation for all work covered by this provision including all materials, construction, maintenance, and removal of Gravel Construction Entrance as directed by the Engineer.

**Permanent Soil Reinforcement Mat:****General:**

This work shall consist of furnishing and placing "Permanent Soil Reinforcement Mat", of the type specified, over previously prepared areas as directed by the Engineer.

**Materials:**

The product shall be permanent erosion control reinforcement mat and shall be constructed of 100% coconut fiber stitch bonded between a heavy duty UV stabilized cusped (crimped) netting overlaid with a heavy duty UV stabilized top net. The three nettings shall be stitched together on 1.5 inch (38 mm) centers UV stabilized polyester thread to form a permanent three dimensional structure. The mat shall have the following physical properties:

Property	Test Method	Value	Unit
Ground Cover	Image Analysis	93	%
Thickness	ASTM D1777	0.63 (16)	in (mm)
Mass Per Unit Area	ASTM D3776	0.92 (0.50)	lb/sy (kg/m <sup>2</sup> )
Tensile Strength	ASTM D5035	480 (714.2)	lb/ft (kg/m)
Elongation	ASTM D5035	49	%
Tensile Strength	ASTM D5035	960 (1428.5)	lb/ft (kg/m)
Elongation	ASTM D5035	31	%
Tensile Strength	ASTM D1682	177 (80.3)	lbs (kg)
Elongation	ASTM D1682	22	%
Resiliency	ASTM D1777	>80	%
UV Stability *	ASTM D4355	151 (68.5)	lbs (kg)
Color(Permanent Net)		UV Black	
Porosity (Permanent Net)	Calculated	>95	%
Minimum Filament Diameter (permanent net)	Measured	0.03 (0.8)	in (mm)

\*ASTM D1682 Tensile Strength and % strength retention of material after 1000 hours of exposure in a Xenon-arc weatherometer.

A certification (Type 1, 2, or 3) from the manufacturer showing:

- 1) the chemical and physical properties of the mat used, and
- 2) conformance of the mat with this specification will be required.

Matting shall be installed according to section 1060-8 of the Standard Specifications.

**Soil Preparation:**

All areas to be protected with the mat shall be brought to final grade and seeded in accordance with Section 1660. The surface of the soil shall be smooth, firm, stable and free of rocks, clods, roots or other obstructions which would prevent the mat from lying in direct contact with the soil surface. Areas where the mat is to be placed will not need to be mulched.

**Basis of Payment:**

Payment for this work shall be included in the contract bid price for "Lump Sum - Roadway Construction." Such payment shall be full compensation for furnishing and installing the mat in accordance with this specification, and for all required maintenance.