

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+ 95.00 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	1,500 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,000 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	262 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	1,000 CY		
001C	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0011	0206000000-E	SP	TEMPORARY SHORING - BARRIER SUPPORTED	205 SF		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	56 LF		
0014	0344000000-E	310	18" SIDE DRAIN PIPE	48 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	40 LF		
0016	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	40 LF		
0017	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0019	0986000000-E	SP	GENERIC PIPE ITEM 8" PVC PIPE	5 LF		
002C	0992000000-E	SP	GENERIC PIPE ITEM 8" PVC PIPE ELBOWS	1 EA		
0021	0995000000-E	340	PIPE REMOVAL	40 LF		
0022	1121000000-E	520	AGGREGATE BASE COURSE	180 TON		
0023	1220000000-E	545	INCIDENTAL STONE BASE	250 TON		
0024	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,210 TON		
0025	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	780 TON		
0026	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	840 TON		
0027	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	140 TON		
0028	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100 TON		
0029	2022000000-E	815	SUBDRAIN EXCAVATION	224 CY		
003C	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
0031	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0032	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0033	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0034	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0036	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0037	2556000000-E	846	SHOULDER BERM GUTTER	90 LF		
0038	3030000000-E	862	STEEL BM GUARDRAIL	1,075 LF		
0039	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
004C	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0041	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
0042	3360000000-E	863	REMOVE EXISTING GUARDRAIL	924 LF		
0043	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (WBEAM)	1 EA		
0044	3635000000-E	876	PLAIN RIP RAP, CLASS II	21 TON		
0045	3649000000-E	876	PLAIN RIP RAP, CLASS B	56 TON		
0046	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	871 SY		
0047	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	570 SF		
0048	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	143 SF		
0049	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
005C	4425000000-N	1125	WARNING FLAG SETS	6 EA		
0051	4430000000-N	1130	DRUMS	50 EA		
0052	4435000000-N	1135	CONES	25 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	4446100000-E	SP	BARRICADES (TYPE III)	96 LF		
0054	4450000000-N	1150	FLAGGER	160 HR		
0055	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0056	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	1 EA		
0057	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	100 LF		
0058	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,260 LF		
0059	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,260 LF		
0060	4715000000-E	1205	THERMOPLASTIC RUMBLE STRIP (4" 240 MILS)	440 LF		
0061	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	31,360 LF		
0062	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	180 LF		
0063	6000000000-E	1605	TEMPORARY SILT FENCE	3,075 LF		
0064	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0065	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	320 TON		
0066	6012000000-E	1610	SEDIMENT CONTROL STONE	375 TON		
0067	6015000000-E	1615	TEMPORARY MULCHING	4.5 ACR		
0068	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0069	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.75 TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	6024000000-E	1622	TEMPORARY SLOPE DRAINS	270 LF		
0071	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	5 EA		
0072	6029000000-E	SP	SAFETY FENCE	300 LF		
0073	6030000000-E	1630	SILT EXCAVATION	1,540 CY		
0074	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,600 SY		
0075	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0076	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		
0077	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0078	6087000000-E	1660	MOWING	2.5 ACR		
0079	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
008C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0081	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0082	6108000000-E	1665	FERTILIZER TOPDRESSING	3.75 TON		
0083	6114000000-N	SP	SPECIALIZED HAND MOWING	3 HR		
0084	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0085	6123000000-E	1670	REFORESTATION	0.5 ACR		

**STRUCTURE ITEMS**

0086	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** ( 20 + 95.00 -L-)	Lump Sum	L.S.	
------	--------------	-----	---	----------	------	--

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	145 LF		
0088	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	36 LF		
0089	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	86.51 LF		
009C	8113000000-N	SP	SID INSPECTION	2 EA		
0091	8114000000-N	SP	SPT TESTING	2 EA		
0092	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0093	8116000000-E	SP	CSL TUBES	784 LF		
0094	8161000000-E	420	GROOVING BRIDGE FLOORS	7,792 SF		
0095	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	101.5 CY		
0096	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** ( 20 + 95.00 -L-)	Lump Sum	L.S.	
0097	8217000000-E	425	REINFORCING STEEL (BRIDGE)	25,558 LB		
0098	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,537 LB		
0099	8364000000-E	450	HP12X53 STEEL PILES	840 LF		
010C	8391000000-N	450	STEEL PILE POINTS	24 EA		
0101	8503000000-E	460	CONCRETE BARRIER RAIL	435.09 LF		
0102	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	290 TON		
0103	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	320 SY		
0104	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0105	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0106	8753100000-E	SP	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	2,822.49 LF		
0107	8892000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE WEARING SURFACE	7,884 SF		
1055/Jun08/Q112574.84/D463133580000/E107			Total Amount Of Bid For Entire Project :			

C201254 (B-3664)  
COUNTY: Henderson County

2/16/99

Contract No: C201254  
County: Henderson

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General