

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201273

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION	200000000-N	806	14	EA	RIGHT OF WAY MARKERS	490500000-N	1253	30	EA	SNOWPLOWABLE PAVEMENT MARKERS	603000000-E	1630	40	CY	SILT EXCAVATION
004300000-N	226	Lump Sum		GRADING	226400000-E	840	0.045	CY	PIPE PLUGS	530000000-E	1505	75	TON	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	603600000-E	1631	380	SY	MATTING FOR EROSION CONTROL
005700000-E	226	250	CY	UNDERCUT EXCAVATION	228600000-N	840	3	EA	MASONRY DRAINAGE STRUCTURES	530600000-E	SP	75	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)	603800000-E	SP	300	SY	PERMANENT SOIL REINFORCEMENT MAT
013400000-E	240	180	CY	DRAINAGE DITCH EXCAVATION	236400000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.16	536000000-E	1510	512	LF	6" DI WATER PIPE, PC 350	604200000-E	1632	455	LF	1/4" HARDWARE CLOTH
019500000-E	265	200	CY	SELECT GRANULAR MATERIAL	239600000-N	840	1	EA	FRAME WITH COVER, STD 840.54	541400000-E	1510	166	LF	3/4" COPPER WATER PIPE, TYPE K	606900000-E	1638	135	CY	STILLING BASINS
031400000-E	SP	230	TON	SELECT MATERIAL, CLASS ***** (IV)	240700000-N	840	1	EA	STEEL FRAME WITH TWO GRATES, STD 840.37	548000000-E	1510	375	LB	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	608400000-E	1660	2	ACR	SEEDING & MULCHING
031400000-E	SP	190	TON	SELECT MATERIAL, CLASS ***** (VI)	253500000-E	846	175	LF	***X*** CONCRETE CURB (8" X 18")	551000000-E	1510	2	EA	3/4" CORPORATION STOP	608700000-E	1660	1.5	ACR	MOWING
031800000-E	300	40	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	255600000-E	846	364	LF	SHOULDER BERM GUTTER	554000000-E	1510	1	EA	6" GATE VALVE & VALVE BOX, 200# WP	609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
034400000-E	310	80	LF	18" SIDE DRAIN PIPE	303000000-E	862	525	LF	STEEL BM GUARDRAIL	558200000-E	1510	2	EA	***X*** TAPPING SADDLE (6" X 3/4")	609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
034500000-E	310	52	LF	24" SIDE DRAIN PIPE	304500000-E	862	50	LF	STEEL BM GUARDRAIL, SHOP CURVED	564800000-N	1510	5	EA	RELOCATE EXISTING WATER METER	609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
036600000-E	310	40	LF	15" RC PIPE CULVERTS, CLASS III	315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	567200000-N	1510	2	EA	RELOCATE EXISTING FIRE HYDRANT	611100000-E	SP	310	LF	IMPERVIOUS DIKE
037200000-E	310	168	LF	18" RC PIPE CULVERTS, CLASS III	319500000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1	569600000-E	1520	222	LF	8" PVC SEWER PIPE, SDR ** (35)	611400000-N	SP	1	HR	SPECIALIZED HAND MOWING
045300000-E	310	6	EA	*** PIPE END SECTION (18")	327000000-N	SP	2	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	579800000-E	1530	198	LF	FILL OR REMOVE ABANDONED *** PIPE, ***** (8", VC SEWER)	611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
045300000-E	310	2	EA	*** PIPE END SECTION (24")	328500000-N	SP	1	EA	GUARDRAIL ANCHOR UNITS, TYPE M-350	600000000-E	1605	950	LF	TEMPORARY SILT FENCE	612000000-E	SP	300	CY	CULVERT DIVERSION CHANNEL
058800000-E	310	24	LF	18" CS PIPE CULVERTS, 0.064" THICK	362800000-E	876	119	TON	PLAIN RIP RAP, CLASS I	600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A					
063600000-E	310	2	EA	*** CS PIPE ELBOWS, ***** (18", 0.064")	363500000-E	876	215	TON	PLAIN RIP RAP, CLASS II	600900000-E	1610	210	TON	STONE FOR EROSION CONTROL, CLASS B					
099500000-E	340	264	LF	PIPE REMOVAL	364900000-E	876	21	TON	PLAIN RIP RAP, CLASS B	601200000-E	1610	200	TON	SEDIMENT CONTROL STONE					
122000000-E	545	150	TON	INCIDENTAL STONE BASE	365600000-E	876	1,025	SY	FILTER FABRIC FOR DRAINAGE	601500000-E	1615	2	ACR	TEMPORARY MULCHING					
148900000-E	610	315	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	365900000-N	SP	1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	601800000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING					
149800000-E	610	390	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	441200000-E	SP	242	SF	WORK ZONE SIGNS (STATIONARY)	602100000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING					
151900000-E	610	675	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	441220000-E	SP	30	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	602400000-E	1622	85	LF	TEMPORARY SLOPE DRAINS					
156000000-E	620	75	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	444610000-E	SP	80	LF	BARRICADES (TYPE III)	602700000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS					
169300000-E	654	8	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	468500000-E	1205	2,100	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	602900000-E	SP	500	LF	SAFETY FENCE					
					468600000-E	1205	2,100	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)										

5/28/99

20-APR-2005 13:59
162300000-N.dwg
162300000-N.dwg