

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

STATE PROJECT REFERENCE NO. <b>B-3834</b>	SHEET NO. TCP-1
--	--------------------

**PLAN FOR PROPOSED  
TRAFFIC CONTROL, MARKING & DELINEATION  
DAVIDSON COUNTY**

**B-3834**

**ROADWAY STANDARD DRAWINGS**

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - ROADWAY DESIGN UNIT-N.C. DEPARTMENT OF TRANSPORTATION-RALEIGH, N.C., DATED JANUARY 2002 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1101.03	TEMPORARY ROAD CLOSURES
1101.05	WORK ZONE VEHICLE ACCESSES
1101.11	TRAFFIC CONTROL DESIGN TABLES
1110.01	STATIONARY WORK ZONE SIGNS
1205.01	PAVEMENT MARKINGS - LINE TYPES & OFFSETS
1205.02	PAVEMENT MARKINGS - 2 LANE & MULTILANE ROADWAYS
1205.12	PAVEMENT MARKINGS - BRIDGES
1250.01	PAVEMENT MARKING SPACING
1253.01	SNOWPLOWABLE RAISED PAVEMENT MARKER
1261.01	GUARDRAIL & BARRIER DELINEATOR SPACING
1261.02	GUARDRAIL & BARRIER DELINEATOR TYPES
1262.01	GUARDRAIL END DELINEATION

**INDEX OF SHEETS**

SHEET NO.	TITLE
TCP-1	LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, LEGEND, INDEX OF SHEETS AND PAVEMENT MARKING SCHEDULE
TCP-2	GENERAL NOTES AND PHASING
TCP-3	OFFSITE DETOUR MAP AND SIGNING
TCP-4	PAYNE ROAD SIGN DETAIL
TCP-5	REPLACEMENT DETAIL FOR RSD 1145.01(BARRICADES TYPE-III)

**LEGEND**

- GENERAL**
- DIRECTION OF TRAFFIC FLOW
  - NORTH ARROW
  - PROPOSED PVMT.    EXIST. PVMT.
  - WORK AREA
  - REMOVAL OF EXISTING PAVEMENT
- TRAFFIC CONTROL DEVICES**
- TYPE I BARRICADE
  - TYPE II BARRICADE
  - TYPE III BARRICADE
  - CONE
  - DRUM
  - FLASHING ARROW PANEL (TYPE C)
  - TYPE 'B' WARNING LIGHT
  - STATIONARY SIGN
  - PORTABLE SIGN
  - STATIONARY OR PORTABLE SIGN
  - WARNING FLAGS
  - CRASH CUSHION
  - CHANGEABLE MESSAGE SIGN
  - TRUCK MOUNTED IMPACT ATTENUATOR (TMIA)
  - POLICE
  - FLAGGER
- PAVEMENT MARKINGS**
- CRYSTAL/CRYSTAL PAVEMENT MARKER
  - YELLOW/YELLOW PAVEMENT MARKER
  - CRYSTAL/RED PAVEMENT MARKER
  - PAVEMENT MARKING SYMBOLS

**TIP PROJECT:**

Final Pavement Marking Schedule  
TIP Project # B-3834

SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY BREAKDOWN	TOTAL QUANTITY
<b>PAVEMENT MARKINGS</b>				
TA	WHITE EDGELINE	THERMOPLASTIC (4" 90 MILS)	2100 LF	TOTAL 2100 LF
TI	YELLOW DOUBLE CENTER	THERMOPLASTIC (4" 120 MILS)	2100 LF	TOTAL 2100 LF
<b>PAVEMENT MARKERS</b>				
ME	YELLOW & YELLOW	SNOWPLOWABLE	30 EA	TOTAL 30 EA

19-APR-2005 09:30  
\\ets-ccfs01\B3834\Tcp\B3834-fo\_tcp.dgn  
pseymore AT TETC206427

APPROVED: <i>Meredith M. McDiarmid</i> DATE: 4/25/05	PLAN PREPARED BY: N.C.D.O.T. WORK ZONE TRAFFIC CONTROL UNIT
SEAL 	J. S. BOURNE, P.E. TRAFFIC CONTROL ENGINEER M. M. MCDIARMID, P.E. TRAFFIC CONTROL PROJECT ENGINEER J. P. GALLOWAY, P.E. TRAFFIC CONTROL PROJECT DESIGN ENGINEER P. SEYMORE TRAFFIC CONTROL DESIGN ENGINEER / TECHNICIAN