



PROJECT SPECIAL PROVISIONS
Utility Construction

GENERAL CONSTRUCTION REQUIREMENTS:

Specifications:

The proposed utility construction shall meet the applicable requirements of the NC Department of Transportation "Standard Specifications for Roads and Structures" dated January 2002 and the provisions outlined below.

Owner and Owner's Requirements:

The existing water and all sanitary sewer belong to the City of Thomasville. The contact person for the city is Mr. Kelly Craver, Assistant City Manager. Mr. Craver can be reached by telephone at (336) 475-4220. The Contractor shall provide access for the owner's representatives to all phases of construction. The owner shall be notified two weeks prior to commencement of any work and one week prior to service interruption. Interruption of water service or force main sewer service on main lines shall be limited to a maximum of 4 hours unless approved by the Engineer.

After the installed pipe, fittings, valves, hydrants, corporation stops and end plugs are inserted and secured, the pipeline shall be subjected to a hydrostatic pressure of 200 PSI for a period of 2 hours, by pumping the section full of clean water using an approved pressure pump. Cross connection for flushing and chlorination shall be made by means of a temporary connection from the supply pipe with an approved backflow prevention device. Cross connection and blowoff piping shall be two inches in diameter for mains eight inches in diameter and smaller, and four inches in diameter for mains greater than eight inches but less than sixteen inches in diameter. Taps for the cross connection piping shall be made to the portion of the existing water main that will be removed from service. The proposed water main shall be laid to within one pipe length of the point of final connection prior to flushing and testing. All flushing and chlorination work shall be performed in accordance with AWWA C651-99. All fittings, valves, backflow prevention devices required for chlorination and testing shall be incidental to the cost of the proposed pipe being tested.

Any cracked, damaged, or defective pipe, fittings, valves, hydrants, or other attachments discovered as a result of the pressure test, shall be removed and replaced with sound material. The tests shall be repeated until test results are satisfactory.

After the pressure test is complete, the Contractor shall make a leakage test. Such leakage test shall last at least 2 hours at a pressure of 200 PSI. The pressure test and leakage test may be performed concurrently.

All valves on the lines being sterilized shall be opened and closed several times during the chlorinating period. The pipeline shall then be flushed with clean water until the residual chlorine is reduced to less than 1.0 ppm or at the same level as in the existing water mains. Samples of water shall be taken at representative points along the pipeline by the Contractor in approved containers and submitted to a certified testing laboratory for bacterial and chlorine content. Test results shall be provided to the City of Thomasville.

Utility Locations Shown on the Plans:

The locations, sizes, and type material of the existing utilities shown on the plans are from the best available information. The Contractor will be responsible for determining the exact location, size, and type material of the existing facilities necessary for the construction of the proposed utilities and to avoid damage to existing facilities.

Dewatering will not be measured and paid for as a separate bid item. All costs involved in dewatering shall be included in the applicable bid item for the various forms of work, i.e. pipe, structures, etc.

Sterilization will not be measured and paid for as a separate bid item. All costs including chlorinating equipment, materials, excavation, barricades, backfilling, and any taps and corporations and re-sterilization shall be included in the applicable bid price for piping and other forms of work.

COMPENSATION:

No direct payment will be made for utility construction work required by the preceding provisions, which are general requirements applying to utility construction, and all of the requirements stated will be considered incidental work, paid for at the contract unit prices of the various utility items included in the contract.

BEDDING MATERIAL:

Bedding material for utility lines shall be installed in accordance with the applicable utility provisions herein, as shown on the utility construction plans, and/or as directed by the Engineer.

Bedding material shall meet the requirements of Article 1016-3 of the Standard Specifications. Bedding material shall be installed in accordance with Articles 300-6 and 300-7 of the Standard Specifications.

Bedding material installed in accordance with the plans and provisions herein and accepted, will be measured and paid for at the contract unit price per ton for "Bedding Material, Utilities Class ____". Such prices and payments shall be full compensation for all materials, labor, equipment, compaction and shaping the bedding material in accordance with Article 300-4 of the Standard Specifications, and incidentals necessary to complete the work as required.

PROJECT SPECIAL PROVISIONS

Utility

UTILITIES BY OTHERS

General:

The following utility companies have facilities that will be in conflict with the construction of this project.

- A) Duke Energy (Distribution)
- B) North State Telephone
- C) Piedmont Natural Gas

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owner. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105-8 of the Standard Specifications.

Utilities Requiring Adjustment:

- A) Duke Energy (Distribution)

- 1) See Utilities by Others Plans.

NOTE: Duke Energy will complete relocations of their existing power distribution facilities to the new locations as shown on the utilities by others plans by the date of availability.

- B) North State Telephone

- 1) See Utilities by Others Plans.

NOTE: North State Telephone will remain in joint use with Duke Energy as shown on the utilities by others plans.



C) Piedmont Natural Gas

- 1) See Utilities by Others Plans.

NOTE: Piedmont Natural Gas will remain in place to be adjusted as necessary.

NOTE: All other utilities will remain in place and will be adjusted as necessary.