

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0004	0134000000-E	240	DRAINAGE DITCH EXCAVATION	180 CY		
0005	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0006	0314000000-E	SP	SELECT MATERIAL, CLASS ***** (IV)	230 TON		
0007	0314000000-E	SP	SELECT MATERIAL, CLASS ***** (VI)	190 TON		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	40 TON		
0009	0344000000-E	310	18" SIDE DRAIN PIPE	80 LF		
0010	0345000000-E	310	24" SIDE DRAIN PIPE	52 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	40 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	168 LF		
0013	0453000000-E	310	*** PIPE END SECTION (18")	6 EA		
0014	0453000000-E	310	*** PIPE END SECTION (24")	2 EA		
0015	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	24 LF		
0016	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (18", 0.064")	2 EA		
0017	0995000000-E	340	PIPE REMOVAL	264 LF		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	315 TON		
002C	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	390 TON		
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE 59.5B	675 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	75 TON		
0023	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	8 TON		
0024	2000000000-N	806	RIGHT OF WAY MARKERS	14 EA		
0025	2264000000-E	840	PIPE PLUGS	0.045 CY		
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0027	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0028	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0029	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	1 EA		
003C	2535000000-E	846	***X*** CONCRETE CURB (8" X 18")	175 LF		
0031	2556000000-E	846	SHOULDER BERM GUTTER	364 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	525 LF		
0033	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0037	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	1 EA		
0038	3628000000-E	876	PLAIN RIP RAP, CLASS I	119 TON		
0039	3635000000-E	876	PLAIN RIP RAP, CLASS II	215 TON		
004C	3649000000-E	876	PLAIN RIP RAP, CLASS B	21 TON		
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,025 SY		
0042	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0043	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	242 SF		
0044	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	30 SF		
0045	4446100000-E	SP	BARRICADES (TYPE III)	80 LF		
0046	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,100 LF		
0047	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,100 LF		
0048	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	30 EA		
0049	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	75 TON		
005C	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)	75 TON		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0051	5360000000-E	1510	6" DI WATER PIPE, PC 350	512 LF		
0052	5414000000-E	1510	3/4" COPPER WATER PIPE, TYPE K	166 LF		
0053	5480000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	375 LB		
0054	5510000000-E	1510	3/4" CORPORATION STOP	2 EA		
0055	5540000000-E	1510	6" GATE VALVE & VALVE BOX, 200# WP	1 EA		
0056	5582000000-E	1510	***X*** TAPPING SADDLE (6" X 3/4")	2 EA		
0057	5648000000-N	1510	RELOCATE EXISTING WATER METER	5 EA		
0058	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	2 EA		
0059	5696000000-E	1520	8" PVC SEWER PIPE, SDR ** (35)	222 LF		
0060	5798000000-E	1530	FILL OR REMOVE ABANDONED *** PIPE, ***** (8", VC SEWER)	198 LF		
0061	6000000000-E	1605	TEMPORARY SILT FENCE	950 LF		
0062	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0063	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	210 TON		
0064	6012000000-E	1610	SEDIMENT CONTROL STONE	200 TON		
0065	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0066	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0067	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0068	6024000000-E	1622	TEMPORARY SLOPE DRAINS	85 LF		
0069	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
007C	6029000000-E	SP	SAFETY FENCE	500 LF		
0071	6030000000-E	1630	SILT EXCAVATION	40 CY		
0072	6036000000-E	1631	MATTING FOR EROSION CONTROL	380 SY		
0073	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	300 SY		
0074	6042000000-E	1632	1/4" HARDWARE CLOTH	455 LF		
0075	6069000000-E	1638	STILLING BASINS	135 CY		
0076	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0077	6087000000-E	1660	MOWING	1.5 ACR		
0078	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0079	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
008C	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0081	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0082	6111000000-E	SP	IMPERVIOUS DIKE	310 LF		
0083	6114000000-N	SP	SPECIALIZED HAND MOWING	1 HR		
0084	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0085	6120000000-E	SP	CULVERT DIVERSION CHANNEL	300 CY		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
CULVERT ITEMS						
0086	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+64.10 -L-)	Lump Sum	L.S.	
0087	8126000000-N	414	CULVERT EXCAVATION, STA ***** (16+64.10 -L-)	Lump Sum	L.S.	
0088	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	134 TON		
0089	8196000000-E	420	CLASS A CONCRETE (CULVERT)	212.8 CY		
009C	8245000000-E	425	REINFORCING STEEL (CULVERT)	35,667 LB		
0749/Jun30/Q52258.595/D356920400000/E90			Total Amount Of Bid For Entire Project :			

C201273 (B-3834)
COUNTY: Davidson County

2/16/99

Contract No: C201273
County: Davidson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General