

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES



STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201230					STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201230					STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201230				
ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	2286000000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES	6024000000-E	1622	60	LF	TEMPORARY SLOPE DRAINS
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING	2365000000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.22	6027000000-N	1622	1	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
0022000000-E	225	2,600	CY	UNCLASSIFIED EXCAVATION	2570000000-N	SP	1	EA	MODIFIED CONCRETE FLUME	6029000000-E	SP	500	LF	SAFETY FENCE
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+25.50)	2619000000-E	850	3	SY	4" CONCRETE PAVED DITCH	6030000000-E	1630	620	CY	SILT EXCAVATION
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING	3030000000-E	862	125	LF	STEEL BM GUARDRAIL	6036000000-E	1631	400	SY	MATting FOR EROSION CONTROL
0057000000-E	226	200	CY	UNDERCUT EXCAVATION	3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	6042000000-E	1632	20	LF	1/4" HARDWARE CLOTH
0063000000-N	SP	Lump Sum		GRADING	3180000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (TYPE III, SHOP CURVED)	6070000000-N	SP	8	EA	SPECIAL STILLING BASINS
0080000000-E	SP	200	TON	CLASS IV SUBGRADE STABILIZATION	3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	6084000000-E	1660	1	ACR	SEEDING & MULCHING
0195000000-E	265	200	CY	SELECT GRANULAR MATERIAL	3649000000-E	876	130	TON	PLAIN RIP RAP, CLASS B	6087000000-E	1660	1	ACR	MOWING
0196000000-E	270	200	SY	FABRIC FOR SOIL STABILIZATION	3656000000-E	876	880	SY	FILTER FABRIC FOR DRAINAGE	6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
0318000000-E	300	10	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	3659000000-N	SP	1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
0344000000-E	310	36	LF	18" SIDE DRAIN PIPE	4412000000-E	SP	48	SF	WORK ZONE SIGNS (STATIONARY)	6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
0582000000-E	310	40	LF	15" CS PIPE CULVERTS, 0.064" THICK	4412100000-E	SP	288	SF	WORK ZONE SIGNS (PORTABLE)	6108000000-E	1665	0.75	TON	FERTILIZER TOPDRESSING
0995000000-E	340	40	LF	PIPE REMOVAL	4412200000-E	SP	64	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	6114000000-N	SP	1	HR	SPECIALIZED HAND MOWING
1220000000-E	545	150	TON	INCIDENTAL STONE BASE	4425000000-N	1125	2	EA	WARNING FLAG SETS	6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
1330000000-E	607	50	SY	INCIDENTAL MILLING	4435000000-N	1135	40	EA	CONES	6123000000-E	1670	0.3	ACR	REFORESTATION
1489000000-E	610	340	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	4446100000-E	SP	32	LF	BARRICADES (TYPE III)					
1525000000-E	SP	155	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	4455000000-N	1150	730	MD	FLAGGER					
1560000000-E	620	25	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	6000000000-E	1605	920	LF	TEMPORARY SILT FENCE					
2022000000-E	815	50	CY	SUBDRAIN EXCAVATION	6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A					
2033000000-E	815	40	CY	SUBDRAIN FINE AGGREGATE	6009000000-E	1610	150	TON	STONE FOR EROSION CONTROL, CLASS B					
2044000000-E	815	200	LF	6" PERFORATED SUBDRAIN PIPE	6012000000-E	1610	235	TON	SEDIMENT CONTROL STONE					
2055000000-E	815	6	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6015000000-E	1615	1	ACR	TEMPORARY MULCHING					
2066000000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING					
2077000000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)	6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING					