Rev 3/6/01

Note: Approximate quantities only. Borrow Excavation, Shoulder Borrow, Fine Grading, Clearing and Grubbing, Breaking of Existing Pavement and Removal of Existing Pavement will be paid for at the contract Lump Sum price for "Grading".

EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

CROSS–SECTION SUMMARY

IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	EMBANKMENT
-L-		
13+00	0	0
13+50	6	4
14+00	12	6
14+50	12	17
15+00	20	72
15+50	28	137
15+68	10	349
16+83	0	538
17+00	5	132
17+50	59	311
18+00	104	143
18+50	345	45
19+00	765	21
19+50	784	6
20+00	426	98
20+50	204	174
21+00	82	80

LOCATION	UNCLASSIFIED EXCAVATION	EMBANKMENT

LOCATION	UNCLASSIFIED EXCAVATION	EMBANKMENT

01/21/2005
r:\Roadway\Xso\b3666_Rdy_Xpl.dgn
8:36:37 AM