

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0022000000-E	225	UNCLASSIFIED EXCAVATION	2,600 CY		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+25.50)	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	200 TON		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
001C	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	36 LF		
0013	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	40 LF		
0014	0995000000-E	340	PIPE REMOVAL	40 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0016	1330000000-E	607	INCIDENTAL MILLING	50 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	340 TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	155 TON		
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	25 TON		
002C	2022000000-E	815	SUBDRAIN EXCAVATION	50 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	40 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0023	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0024	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0025	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0027	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		
0028	2570000000-N	SP	MODIFIED CONCRETE FLUME	1 EA		
0029	2619000000-E	850	4" CONCRETE PAVED DITCH	3 SY		
003C	3030000000-E	862	STEEL BM GUARDRAIL	125 LF		
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0032	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (TYPE III, SHOP CURVED)	4 EA		
0033	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0034	3649000000-E	876	PLAIN RIP RAP, CLASS B	130 TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	880 SY		
0036	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0037	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	48 SF		
0038	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	288 SF		
0039	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	64 SF		
004C	4425000000-N	1125	WARNING FLAG SETS	2 EA		
0041	4435000000-N	1135	CONES	40 EA		
0042	4446100000-E	SP	BARRICADES (TYPE III)	32 LF		
0043	4455000000-N	1150	FLAGGER	730 MD		
0044	6000000000-E	1605	TEMPORARY SILT FENCE	920 LF		
0045	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0046	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	150 TON		
0047	6012000000-E	1610	SEDIMENT CONTROL STONE	235 TON		
0048	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0049	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
005C	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0051	6024000000-E	1622	TEMPORARY SLOPE DRAINS	60 LF		
0052	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	6029000000-E	SP	SAFETY FENCE	500 LF		
0054	6030000000-E	1630	SILT EXCAVATION	620 CY		
0055	6036000000-E	1631	MATTING FOR EROSION CONTROL	400 SY		
0056	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		
0057	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0058	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0059	6087000000-E	1660	MOWING	1 ACR		
0060	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0062	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0063	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0064	6114000000-N	SP	SPECIALIZED HAND MOWING	1 HR		
0065	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0066	6123000000-E	1670	REFORESTATION	0.3 ACR		

**STRUCTURE ITEMS**

0067	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (16 + 25.50 -L-)	Lump Sum	L.S.	
0068	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 25.50 -L-)	Lump Sum	L.S.	

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	16.75 LF		
007C	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	9 LF		
0071	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	13.27 LF		
0072	8113000000-N	SP	SID INSPECTION	1 EA		
0073	8114000000-N	SP	SPT TESTING	4 EA		
0074	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0075	8116000000-E	SP	CSL TUBES	143 LF		
0076	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16 + 25.50 -L-)	Lump Sum	L.S.	
0077	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	58.1 CY		
0078	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16 + 25.50 -L-)	Lump Sum	L.S.	
0079	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,746 LB		
008C	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,356 LB		
0081	8364000000-E	450	HP12X53 STEEL PILES	100 LF		
0082	8391000000-N	450	STEEL PILE POINTS	10 EA		
0083	8503000000-E	460	CONCRETE BARRIER RAIL	225.5 LF		
0084	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	275 TON		
0085	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	310 SY		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0086	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0087	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,125 LF		

1600/Jun30/Q25465.17/D399728480000/E87

**Total Amount Of Bid For Entire Project :**

C201230 (B-3666)  
COUNTY: Henderson County

2/16/99

Contract No: C201230  
County: Henderson

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General