

PROJECT REFERENCE NUMBER	SHEET NO.	TOTAL SHEETS
	3B	7
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION

PROJECT: B-3681 COUNTY: Nash / Edgecombe DATE: 5/23/05 Volumes in Cubic Yards COMPILED BY: DAP SHEET 1 OF 1

STATION	STATION	EXCAVATION				EMBANKMENT				BORROW	WASTE				
		TOTAL UNCLASS.	ROCK	UNDERCUT	UNSUIT. UNCLASS.	SUITABLE UNCLASS.	TOTAL	ROCK	EARTH		EMBANK. (+) 25%	ROCK	SUITABLE	UNSUIT.	TOTAL
-L- 10+00.00	17+64.64 BRIDGE	174				174	13,991		13,991	17,489	17,315				
-L- 19+96.89	30+00.00 BRIDGE	373				373	14,309		14,309	17,886	17,513				
	SUBTOTAL	547				547	28,300		28,300	35,375	34,828				
	TOTAL	547				547	28,300		28,300	35,375	34,828				
PROJECT	TOTALS	547				547	28,300		28,300	35,375	34,828				
	EST. 5% FOR REPLACING TOPSOIL ON BORROW PITS										1,741				
GRAND	TOTALS	547				547	28,300		28,300	35,375	36,569				
SAY		550								35,380	36,570				
	EST. UNDERCUT = 500 CY.														
	EST. DDE = 1,510 CY.														