

**STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS**

CROSS-SECTION SUMMARY

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
-L-		
10+00.00	0	0
10+50.00	25	6
11+00.00	31	15
11+50.00	21	42
12+00.00	31	159
12+50.00	26	351
13+00.00	16	511
13+50.00	12	612
14+00.00	7	672
14+50.00	4	809
15+00.00	1	1022
15+50.00	0	1205
16+00.00	0	1361
16+50.00	0	1467
17+00.00	0	1761
17+50.00	0	1999
17+64.64 (BEG. BRIDGE)	0	1999
19+96.89 (END BRIDGE)	0	61
20+00.00	0	61
20+50.00	0	1973
21+00.00	0	1921
21+50.00	0	1746
22+00.00	0	1530
22+50.00	3	1299
23+00.00	9	1080
23+50.00	12	890
24+00.00	19	737
24+50.00	26	644
25+00.00	32	548
25+50.00	40	430
26+00.00	51	361
26+50.00	60	311
27+00.00	37	284
27+50.00	13	226
28+00.00	12	127
28+50.00	16	58
29+00.00	20	17
29+50.00	23	5
30+00.00	0	0
TOTAL	547	28300

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.