

PROJECT: B-3681
COUNTY: NASH- EDGECOMBE

PROJECT SPECIAL PROVISIONS
Utility

UTILITIES BY OTHERS:

General:

The following utility companies have facilities that will be in conflict with the construction of this project.

- A. City of Rocky Mount (Water)
- B. City of Rocky Mount (Power)
- C. City of Rocky Mount (Gas)
- D. Sprint (Telephone)
- E. Quest Communications
- F. MCI

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions and shown on the Utilities By Others for the benefit of the Contractor. All utility work listed herein will be done by the utility owners unless otherwise noted. All utilities are shown on the plans from the best available information. For utility relocations see the Utilities By Others Plans.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

- A. City of Rocky Mount (Water)
 - 1. Note: All existing water lines located within the limits of this project will remain in place and be adjusted if necessary.
 - 2. See Utilities By Others Plans.
- B. City of Rocky Mount (Power)
 - 1. The existing power line crossing Line-L- at Sta. 16+65± has been dismantled and removed. The existing power poles will be removed before date of availability.
 - 2. See Utilities By Others Plans for details.
- C. City of Rocky Mount (Gas)
 - 1. Note: All existing buried gas lines located within the limits of this project will remain in place and be adjusted if necessary.
 - 2. See Utilities By Others Plans.

D. Sprint (Telephone)

1. All existing buried and aerial telephone located within the limits of the project will remain in place and be adjusted as necessary. All pedestals will be adjusted as required.
2. See Utilities By Others Plans.

E. Quest Communications

1. The existing buried fiber optic cables located west of the CSX Railroad and crossing Line-L-at Sta.18+70± will remain in place. The Contractor will install temporary steel protector plates over the existing buried fiber optic cables at locations that the existing bridge columns are to be removed.
2. All other existing buried fiber optic cables will remain in place and be adjusted as necessary.
3. See Structure Special Provisions and Utilities By Others Plans.

F. MCI

1. Sta.10+30± to Sta.10+90± Line-Y1-
The existing buried fiber optic cables located east of Line-Y1- located from Sta.10+30± to Sta.10+90± will remain in place and will be wrapped in a split-casing conduit.
2. All existing buried fiber optic cables located east of the CSX Railroad and crossing Line-L-at Sta.19+15± will remain in place. The Contractor will install temporary steel protector plates over the existing buried fiber optic cables at locations that the existing bridge columns are to be removed.
3. All other existing buried fiber optic cables will remain in place and be adjusted as necessary.
4. See Structure Special Provisions and Utilities By Others Plans for details.