

County : Edgemcombe, Nash

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|--------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0001000000-E | 200 | CLEARING & GRUBBING .. ACRE(S) | Lump Sum | L.S. | |
| 0003 | 0008000000-E | 200 | SUPPLEMENTARY CLEARING & GRUB- BING | 1 ACR | | |
| 0004 | 0022000000-E | 225 | UNCLASSIFIED EXCAVATION | 550 CY | | |
| 0005 | 0029000000-N | SP | REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+80.77) | Lump Sum | L.S. | |
| 0006 | 0036000000-E | 225 | UNDERCUT EXCAVATION | 500 CY | | |
| 0007 | 0106000000-E | 230 | BORROW EXCAVATION | 36,570 CY | | |
| 0008 | 0134000000-E | 240 | DRAINAGE DITCH EXCAVATION | 1,510 CY | | |
| 0009 | 0156000000-E | 250 | REMOVAL OF EXISTING ASPHALT PAVEMENT | 2,900 SY | | |
| 0010 | 0195000000-E | 265 | SELECT GRANULAR MATERIAL | 200 CY | | |
| 0011 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 200 SY | | |
| 0012 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 29 TON | | |
| 0013 | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 112 LF | | |
| 0014 | 0372000000-E | 310 | 18" RC PIPE CULVERTS, CLASS III | 4 LF | | |
| 0015 | 0708000000-E | 310 | 15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 156 LF | | |
| 0016 | 0806000000-E | 310 | 15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK (15", 0.064") | 4 EA | | |
| 0017 | 0995000000-E | 340 | PIPE REMOVAL | 98 LF | | |
| 0018 | 0996000000-N | 350 | PIPE CLEAN-OUT | 1 EA | | |

County : Edgecombe, Nash

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 0019 | 1011000000-N | 500 | FINE GRADING | Lump Sum | L.S. | |
| 0020 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 200 TON | | |
| 0021 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 1,175 TON | | |
| 0022 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 1,000 TON | | |
| 0023 | 1519000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 1,100 TON | | |
| 0024 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 164 TON | | |
| 0025 | 2000000000-N | 806 | RIGHT OF WAY MARKERS | 8 EA | | |
| 0026 | 2253000000-E | 840 | PIPE COLLARS | 0.5 CY | | |
| 0027 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 5 EA | | |
| 0028 | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 4 EA | | |
| 0029 | 2374000000-N | 840 | FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G) | 1 EA | | |
| 0030 | 2549000000-E | 846 | 2'-6" CONCRETE CURB & GUTTER | 150 LF | | |
| 0031 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 80 LF | | |
| 0032 | 2647000000-E | 852 | 5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED) | 60 SY | | |
| 0033 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 2,400 LF | | |
| 0034 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 0035 | 3215000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE III | 4 EA | | |
| 0036 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 4 EA | | |

County : Edgecombe, Nash

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 0037 | 3360000000-E | 863 | REMOVE EXISTING GUARDRAIL | 2,866 LF | | |
| 0038 | 3649000000-E | 876 | PLAIN RIP RAP, CLASS B | 5 TON | | |
| 0039 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 245 SY | | |
| 0040 | 3659000000-N | SP | PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON | 1 EA | | |
| 0041 | 4025000000-E | 901 | CONTRACTOR FURNISHED, TYPE *** SIGN (D) | 34.5 SF | | |
| 0042 | 4025000000-E | 901 | CONTRACTOR FURNISHED, TYPE *** SIGN (E) | 18.84 SF | | |
| 0043 | 4025000000-E | 901 | CONTRACTOR FURNISHED, TYPE *** SIGN (F) | 95.69 SF | | |
| 0044 | 4072000000-E | 903 | SUPPORTS, 3-LB STEEL U-CHANNEL | 358 LF | | |
| 0045 | 4096000000-N | 904 | SIGN ERECTION, TYPE D | 4 EA | | |
| 0046 | 4102000000-N | 904 | SIGN ERECTION, TYPE E | 5 EA | | |
| 0047 | 4108000000-N | 904 | SIGN ERECTION, TYPE F | 7 EA | | |
| 0048 | 4129000000-N | 906 | RELOCATE SIGN, TYPE ***** (E) | 3 EA | | |
| 0049 | 4155000000-N | 907 | DISPOSAL OF SIGN SYSTEM, U- CHANNEL | 14 EA | | |
| 0050 | 4158000000-N | 907 | DISPOSAL OF SIGN SYSTEM, WOOD | 8 EA | | |
| 0051 | 4192000000-N | 907 | DISPOSAL OF SUPPORT, U-CHANNEL | 2 EA | | |
| 0052 | 4412000000-E | SP | WORK ZONE SIGNS (STATIONARY) | 404 SF | | |
| 0053 | 4412100000-E | SP | WORK ZONE SIGNS (PORTABLE) | 148 SF | | |
| 0054 | 4412200000-E | SP | WORK ZONE SIGNS (BARRICADE MOUNTED) | 94 SF | | |

County : Edgecombe, Nash

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 0055 | 4415000000-N | 1115 | FLASHING ARROW PANELS, TYPE C | 1 EA | | |
| 0056 | 4425000000-N | 1125 | WARNING FLAG SETS | 4 EA | | |
| 0057 | 4430000000-N | 1130 | DRUMS | 50 EA | | |
| 0058 | 4435000000-N | 1135 | CONES | 50 EA | | |
| 0059 | 4446100000-E | SP | BARRICADES (TYPE III) | 96 LF | | |
| 0060 | 4450000000-N | 1150 | FLAGGER | 48 HR | | |
| 0061 | 4480000000-N | 1165 | TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH) | 1 EA | | |
| 0062 | 4685000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS) | 4,023 LF | | |
| 0063 | 4686000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS) | 5,661 LF | | |
| 0064 | 4695000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS) | 117 LF | | |
| 0065 | 4710000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS) | 236 LF | | |
| 0066 | 4725000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) | 15 EA | | |
| 0067 | 4900000000-N | 1252 | PERMANENT RAISED PAVEMENT MARKERS | 52 EA | | |
| 0068 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 2,160 LF | | |
| 0069 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 115 TON | | |
| 0070 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 555 TON | | |
| 0071 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 225 TON | | |
| 0072 | 6015000000-E | 1615 | TEMPORARY MULCHING | 3.5 ACR | | |
| 0073 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 150 LB | | |

County : Edgecombe, Nash

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0074 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 0.5 TON | | |
| 0075 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 275 LF | | |
| 0076 | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 8 EA | | |
| 0077 | 6030000000-E | 1630 | SILT EXCAVATION | 2,430 CY | | |
| 0078 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 1,575 SY | | |
| 0079 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 60 LF | | |
| 0080 | 6084000000-E | 1660 | SEEDING & MULCHING | 6 ACR | | |
| 0081 | 6087000000-E | 1660 | MOWING | 2 ACR | | |
| 0082 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |
| 0083 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 0084 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 75 LB | | |
| 0085 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 4.25 TON | | |
| 0086 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 5.5 HR | | |
| 0087 | 6117000000-N | 1675 | RESPONSE FOR EROSION CONTROL | 8 EA | | |
| 0088 | 7060000000-E | 1705 | SIGNAL CABLE | 1,920 LF | | |
| 0089 | 7120000000-E | 1705 | VEHICLE SIGNAL HEAD (12", 3 SECTION) | 14 EA | | |
| 0090 | 7144000000-E | 1705 | VEHICLE SIGNAL HEAD (12", 5 SECTION) | 2 EA | | |
| 0091 | 7252000000-E | 1710 | MESSENGER CABLE (1/4") | 140 LF | | |
| 0092 | 7279000000-E | 1715 | TRACER WIRE | 1,090 LF | | |
| 0093 | 7300000000-E | 1715 | TRENCHING (UNPAVED) | 1,004 LF | | |

County: Edgecombe, Nash

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 0094 | 7301000000-E | SP | DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ***** (** CONDUIT) (2", 1) | 145 LF | | |
| 0095 | 7301000000-E | SP | DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ***** (** CONDUIT) (2", 2) | 305 LF | | |
| 0096 | 7301000000-E | SP | DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ***** (** CONDUIT) (2", 3) | 125 LF | | |
| 0097 | 7324000000-N | 1716 | JUNCTION BOX (STANDARD SIZE) | 17 EA | | |
| 0098 | 7336000000-N | 1716 | JUNCTION BOX (OVER-SIZED) | 7 EA | | |
| 0099 | 7360000000-N | 1720 | WOOD POLE | 1 EA | | |
| 0100 | 7372000000-N | 1721 | GUY ASSEMBLY | 2 EA | | |
| 0101 | 7420000000-E | 1722 | 2" RISER WITH WEATHERHEAD | 1 EA | | |
| 0102 | 7432000000-E | 1722 | 2" RISER WITH HEAT SHRINK TUBING | 1 EA | | |
| 0103 | 7444000000-E | 1725 | INDUCTIVE LOOP SAWCUT | 1,960 LF | | |
| 0104 | 7456000000-E | 1726 | LEAD-IN CABLE | 1,780 LF | | |
| 0105 | 7564000000-N | 1732 | FIBER-OPTIC TRANSCEIVER | 1 EA | | |
| 0106 | 7566000000-N | 1733 | DELINEATOR MARKER | 5 EA | | |
| 0107 | 7574000000-N | SP | FURNISH FIBER-OPTIC TRANSCEIVER | 1 EA | | |
| 0108 | 7588000000-N | 1741 | SIGNAL SUPPORT MAST ARM WITH METAL POLE | 3 EA | | |
| 0109 | 7590000000-N | SP | DOUBLE MAST ARM WITH METAL POLE | 1 EA | | |
| 0110 | 7613000000-N | SP | SOIL TEST | 4 EA | | |
| 0111 | 7636000000-N | 1745 | SIGN FOR SIGNALS | 5 EA | | |

County: Edgecombe, Nash

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0112 | 7684000000-N | 1750 | SIGNAL CABINET FOUNDATION | 1 EA | | |
| 0113 | 7816000000-N | SP | DETECTOR UNIT NEMA TS-1 | 2 EA | | |
| 0114 | 7960000000-N | SP | METAL POLE FOUNDATION REMOVAL | 1 EA | | |
| 0115 | 7972000000-N | SP | METAL POLE REMOVAL | 1 EA | | |
| 0116 | 7980000000-N | SP | GENERIC SIGNAL ITEM CCTV CAMERA ASSEMBLY | 1 EA | | |
| 0117 | 7980000000-N | SP | GENERIC SIGNAL ITEM CCTV EQUIPMENT CABINET (BASE MOUNTED) | 1 EA | | |
| 0118 | 7980000000-N | SP | GENERIC SIGNAL ITEM MAST ARM WITH METAL POLE DE- SIGN | 4 EA | | |
| 0119 | 7980000000-N | SP | GENERIC SIGNAL ITEM MMFO INTERCONNECT CENTER | 2 EA | | |
| 0120 | 7980000000-N | SP | GENERIC SIGNAL ITEM MULTIMODE VIDEO/DATA RECEIVER | 1 EA | | |
| 0121 | 7980000000-N | SP | GENERIC SIGNAL ITEM MULTIMODE VIDEO/DATA TRANSMIT- TER | 1 EA | | |
| 0122 | 7980000000-N | SP | GENERIC SIGNAL ITEM SINGLE-MODE VIDEO/DATA RECEIV- ER (FURNISHED ONLY) | 1 EA | | |
| 0123 | 7980000000-N | SP | GENERIC SIGNAL ITEM SINGLE-MODE VIDEO/DATA TRANS- MITTER | 1 EA | | |
| 0124 | 7980000000-N | SP | GENERIC SIGNAL ITEM VIDEO MULTIPLEXER | 1 EA | | |
| 0125 | 7990000000-E | SP | GENERIC SIGNAL ITEM MMFO COMMUNICATIONS CABLE (12 FIBER) | 1,450 LF | | |
| 0126 | 7990000000-E | SP | GENERIC SIGNAL ITEM OPTICAL DETECTOR CABLE | 366 LF | | |

County: Edgecombe, Nash

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-----------|-----------|--------|
| 0127 | 7990000000-E | SP | GENERIC SIGNAL ITEM UNDERGROUND POLYETHYLENE CON- DUIT, 2" (1 CONDUIT) | 945 LF | | |
| 0128 | 7992000000-E | SP | GENERIC SIGNAL ITEM DRILLED PIER FOUNDATION | 48 CY | | |

STRUCTURE ITEMS

| | | | | | | |
|------|--------------|-----|---|---------------|------|--|
| 0129 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+89.64 -L-) | Lump Sum | L.S. | |
| 0130 | 8119000000-E | 412 | UNCLASSIFIED STRUCTURE EXCAVA- TION | 2,900 CY | | |
| 0131 | 8147000000-E | 420 | REINFORCED CONCRETE DECK SLAB | 9,934 SF | | |
| 0132 | 8161000000-E | 420 | GROOVING BRIDGE FLOORS | 10,253 SF | | |
| 0133 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 115.2 CY | | |
| 0134 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (18+89.64 -L-) | Lump Sum | L.S. | |
| 0135 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 17,211 LB | | |
| 0136 | 8280000000-E | 440 | APPROX LBS STRUCTURAL STEEL | 271,900 LS | | |
| 0137 | 8364000000-E | 450 | HP12X53 STEEL PILES | 720 LF | | |
| 0138 | 8385000000-E | 450 | PP ** X **** STEEL PILES (24" X 0.50") | 800 LF | | |
| 0139 | 8503000000-E | 460 | CONCRETE BARRIER RAIL | 459.36 LF | | |
| 0140 | 8531000000-E | 462 | 4" SLOPE PROTECTION | 755 SY | | |
| 0141 | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |

County : Edgecombe, Nash

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---------------------|----------|-----------|--------|
| 0142 | 8692000000-N | SP | EVAZOTE JOINT SEALS | Lump Sum | L.S. | |

0952/Jul11/Q397987.46/D727626500000/E142

Total Amount Of Bid For Entire Project :

C201271 (B-3681)
COUNTIES: Edgecombe-Nash

2/16/99

Contract No: C201271
Counties: Edgecombe-Nash

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General