

PROJ. REFERENCE NO.	SHEET NO.
B-3899	X-1

**STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS**

**CROSS-SECTION SUMMARY**

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDES BACKFILL FOR UNDERCUT

Phase 1			Phase 2			Phase 3		
Station -L-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station -L-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station -L-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+00.00	0	0	12+00.00	0	0	12+00.00	0	0
12+50.00	0	0	12+50.00	68	11	12+50.00	0	0
13+00.00	0	0	13+00.00	148	25	13+00.00	0	0
13+50.00	12	2	13+50.00	217	22	13+50.00	0	0
14+00.00	44	2	14+00.00	277	13	14+00.00	1	0
14+50.00	87	1	14+50.00	299	12	14+50.00	4	9
15+00.00	91	0	15+00.00	303	10	15+00.00	9	12
15+50.00	100	0	15+50.00	242	15	15+50.00	9	12
16+00.00	97	0	16+00.00	167	34	16+00.00	5	19
16+50.00	34	55	16+50.00	101	64	16+50.00	27	16
17+00.00	4	87	17+00.00	72	96	17+00.00	41	15
17+50.00	8	52	17+50.00	138	110	17+50.00	44	21
18+00.00	43	26	18+00.00	236	95	18+00.00	52	25
18+50.00	7	12	18+50.00	260	71	18+50.00	69	29
19+00.00	3	18	19+00.00	227	55	19+00.00	86	41
19+50.00	3	11	19+50.00	130	100	19+50.00	79	52
20+00.00	0	0	20+00.00	26	291	20+00.00	65	67
20+50.00	0	0	20+50.00	0	601	20+50.00	52	78
21+00.00	0	0	21+00.00	0	830	21+00.00	40	66
21+50.00	0	0	21+50.00	0	898	21+50.00	29	53
22+00.00	0	0	22+00.00	0	982	22+00.00	27	38
22+50.00	0	0	22+50.00	0	1100	22+50.00	24	19
23+00.00	0	0	23+00.00	0	1202	23+00.00	9	22
<b>BEG. BRIDGE 23+22.00</b>	0	0	<b>BEG. BRIDGE 23+22.00</b>	0	0	<b>BEG. BRIDGE 23+22.00</b>	0	0
<b>END BRIDGE 24+60.00</b>	0	0	<b>END BRIDGE 24+60.00</b>	0	0	<b>END BRIDGE 24+60.00</b>	0	0
25+00.00	0	0	25+00.00	0	725	25+00.00	0	38
25+50.00	0	0	25+50.00	0	1333	25+50.00	8	108
26+00.00	0	0	26+00.00	0	1022	26+00.00	18	130
26+50.00	0	0	26+50.00	0	631	26+50.00	18	106
27+00.00	0	0	27+00.00	0	341	27+00.00	14	88
27+50.00	0	0	27+50.00	39	199	27+50.00	12	70
28+00.00	0	0	28+00.00	47	172	28+00.00	10	61
28+50.00	0	0	28+50.00	15	123	28+50.00	7	67
29+00.00	0	0	29+00.00	44	43	29+00.00	10	53
29+50.00	0	0	29+50.00	97	34	29+50.00	24	27
30+00.00	0	0	30+00.00	91	33	30+00.00	39	12
30+50.00	0	0	30+50.00	89	30	30+50.00	0	0
31+00.00	0	0	31+00.00	78	27	31+00.00	0	0
31+50.00	0	0	31+50.00	38	25	31+50.00	0	0
32+00.00	0	0	32+00.00	51	25	32+00.00	0	0
32+50.00	0	0	32+50.00	52	41	32+50.00	0	0
33+00.00	0	0	33+00.00	37	45	33+00.00	0	0
33+50.00	0	0	33+50.00	37	43	33+50.00	0	0
34+00.00	0	0	34+00.00	0	0	34+00.00	0	0
<b>TOTAL</b>	<b>533</b>	<b>266</b>	<b>TOTAL</b>	<b>3,626</b>	<b>11,529</b>	<b>TOTAL</b>	<b>832</b>	<b>1,354</b>

NOTE: APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, FINE GRADING, CLEARING & GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING".

